Younkins Replat of Part of Lots 10 till Russell Tracts

B.M. 131.01 Step Spike, E. Side P. Pole, S.E. Cor. 38th & Amidon

31st ST.

NOTE TO CONTRACTOR
If necessary to remove small stumps same shall be bid as lin. ft. of hedge removed.

Gordon Fitz John 3201 Amidon

Sta. 0+00 Exist. M.H. Stub W. Sta. 0+05 Begin. Proj

Sta. 1+64.8 Const. Std. M.H. Type "A"

Sta. 3+00 End Line 1, Plug Pipe

Line 1

Line 2

Sta. 1+64.8 Line 1 & Sta. 0+00 Line 2

B.E. Terrell 3207 Amidon

Thomas C. Cantrell 3211 Amidon

Sta. 1+50 End Line 2, Plug Pipe

AMIDON AVE.

Scale 1" = 40'

Scale 1:40 Horz. 1:4 Vert.

Sta. 0+00 Exist. M.H. Sta. 0+05 Begin. Proj

Sta. 1+64.8 Const. Std. M.H. Type "A"

Sta. 3+00 Plug Pipe End Line No. 1

Sta. 0+00 Exist. M.H. Sta. 0+00 Line No. 2

Sta. 1+50 Plug Pipe End Line No. 2

Proposed N.Gd. 31st St.

Natural Ground

Line No. 1

8" V.C.P. -0.6%

295 Lin. Ft. 8" V.C.P. @ +0.4% Gr.

Proposed W.Gd. Amidon

Line No. 2

8" V.C.P. +0.4%

150 Lin. Ft. 8" V.C.P. @ +0.4% Gr.

LAT. 51, SUB. 17, SS 22
CITY OF WICHITA, KANSAS
B.E. SMITH, CITY ENGINEER
PROJ. NO. C27-65 DATE APRIL 1968

B.M. 126.39 Nail S.S. P.P. 150' W. of Hood N.S. 29th St.

Plan Scale 1"=40'
Profile Scale Horz. 1"=40'
Vert. 1"=4'

Hood Ave.

TIMMERMEYER

60 59 58 57 56

Glen E. Staver 3118 Hood

F.E. Ferrill

W.H.H. Estar. 3116 Hood

C.G. Kreaden

Sta. 0+00 Exist. Manhole with 8" Stub North. Sta. 0+05 Begin Project

Sta. 3+20 Const. Std. Brick Manhole with 8" Stub North. Sta. 3+20

Exist. Ground

Prop. Top of Curb Hood Avenue

320 L.F. 8" V.C.P. @ 0.3%

Sta. 0+00 Flow = 118.85

Sta. 1+00 Flow = 119.15

Sta. 2+00 Flow = 119.45

Sta. 3+00 Flow = 119.75

Sta. 3+20 Flow = 119.81

Survey Young Plan Schneider

Caution: Do not disturb Water Tree

Sta. 0+00 Exist. Manhole with 8" Stub North.

16' Easement

Exist. 8" V.C.P.

N.L. Benefit District

GARDENS

LAT. 67, SUB. 4, SS. 23
CITY OF WICHITA, KANSAS
B. E. SMITH, CITY ENGINEER
PROJ. NO. C 28-47
DATE: JULY 1968