Sta 2+56 Const. Spec. M.H. Type A. Proposed Top of M.H. Elev. = 128.3 Install 4" Stub, NW

Sta 2+14 Const. Spec. M.H. Type A, Proposed Top of M.H. Elev. = 128.26

Sta 0+00 Existing M.H. Top Elev. = 128.34 Remove Existing 8" Stub

Sta 1+70 Const. Spec. M.H. Type A. Prop. Top of M.H. Elev. = 128.3

RACETTE - RIVEREND

33RD ST. NO. CIRCLE

ADDITION

Proposed 24" SWS

@ 20' Drainage Easement

10' Utility Easement

10' Sewer Easement

Existing 8" Water

Prop. 16" Water

*Contact Gas Service Co 263-7511 for Location — 2" Steel Gas Line

SE Cor, NE 1/4 Sec 31-26-1E

Dedication

Drainage

N 89° 53' 45" E 258'

N 0° 06' 15" W 140'

N 89° 53' 45" E 258'

N 0° 06' 15" W 1324'

N 38° 43' 58" E 180.32'

N 36° 24' 55" E 191.76'

N 54° 21' 58" E 68.03'

N 14° 22' 20" W 19.33'

N 22° 01' 18" E 99.36'

N 8° 05' 04" E 84.53'

N 0° 28' 18" E 47.0'

NEW STD. 24" OPENING RING AND COVER

8" BRICK MASONRY

1" COAT OF MORTAR

4'6" MAX.

9"

4" MIN.

6"

FLOOR SHAPING

CITY CONCRETE PAVEMENT MIX

NO. 4 BARS 6" ON CENTER IN BOTH DIRECTIONS

SPECIAL TYPE "A" MANHOLE

Special Type "A" MH

Proposed 24" SWS

130

125

120

256 Lin Ft. 8" ABS Comp. pe @ 0.3% Grade

0 1 1+70 2+56

SCALE - 1" = 40' Plan
Horz. 1" = 40' Profile
Vert. 1" = 5'

Bench Marks: 136.36 City Std. Disc., 42'E and 34'N of ℄ of Amidon & 33rd St. N.

128.34 : T.B.M. East Rim Existing MH, Sta. 0+00 of Lat. 66, Main 17, S.S. No 22.

As Built J.L.L. 9.82

DONALD E. SCHLEGER — LICENSED — 6311 — KANSAS — PROFESSIONAL ENGINEER

LAT. 66, MAIN 17, S.S. NO. 22

CITY OF WICHITA, KANSAS

B. W. BRUGGEMAN

DIRECTOR OF ENGINEERING / CITY ENGINEER

PROJ. NO. 468-76-245-68885-000-000-001

FILMED FROM THE BEST AVAILABLE COPY....