Existing 8" Sanitary Sewer

Underground Telephone Cable Box, Line Runs N-S. On East Side Of Easement.

Sta. 0+00.0 Exist M.H.

Sta. 3+08.0 Const. Std. M.H., Type "A"

Sta. 4+84.0 Const. Std. M.H., Type "A"

Sta. 1+99.3 Const. Std. M.H., Type "A"

Sta. 5+67.0 Const. Std. M.H., Type "A"

PORTER

SHERWOOD GLEN

FRIAR LANE

AVE.

2ND ADDN.

ST. NO.

Note: All Manholes On The East Side Of Porter Ave. Are Centered & West Of The East Property Line Of Porter Ave.

Note: The Correction Of The 6" Clay Pipe To The Existing M.H. (At Sta 0+00.0), Is To Be Considered Incidental To The Other Items Of Work.

Note: The Contractor Is To Maintain A Minimum Cover Of 3.0' Over The Sewer, By Using Excess Excavated Material From This Project.

CAUTION UNDERGROUND UTILITIES

B.M. 139.63 R.R. Spike N.S.P.P. S.S. 37½ - ½ Mi. E. of Meridian

Plan Scale 1" = 40'
Profile Scale 1" = 40' Hor.
1" = 4' Vert.

Sta. 0+00.0 Exist M.H.

Sta. 1+77.1 Const. Std. M.H., Type "A"

Sta. 3+08.0 Const. Std. M.H., Type "A"

Sta. 4+84.0 Const. Std. M.H., Type "A"

Sta. 5+67.0 Const. Std. M.H., Type "A"

Top MH 132.52

Top MH 132.70

Top MH 132.85

Top MH 132.77

130.00

120.00

560 Lin. Ft. Of 8" Clay Pipe @ 0.20% Grade

0+00 1+00 2+00 3+00 4+00 5+00

"As Built" Final Manhole K-111

LATERAL G, SUB. 21, S.S. NO. 22
CITY OF WICHITA, KANSAS
R.W. LINN, CITY ENGINEER
PROJ. NO. DBKL585C26
June 1973

14 2 5 13