B.M. 1131.64 "□" Top W. Cb. Porter 60' N Of Ctr. Line 37th St. North
B.M. 1134.67 SE Cor. Conc. Porch House # 3851 Porter

WOODROW AVE.

PORTER AVE.

37TH ST. NORTH

Sta 6+00 Line 1
Begin 8" Line at Proposed MH.

Sta 3+88.5 Line 1
Const Std MH
Type 'A' or 'C'
8" Stub SSW
End Line 1

Prop 12" Water Line

Existing 8" Sanitary Sewer

Sta 1+92 Line 2
Const Std MH
Type 'A' or 'C'
8" Stub E
8" Stub SE
End Line 2

Temporary Const Esmt.

20' Sewer Esmt.

Joe Borgas Jr.
1427 W. 37th St.
Wichita, Kansas

Sta 1+92 Line 1
= Sta 6+00 Line 2
Const Std MH
Type 'A' or 'C'

A. J. SOERRIES ADDN.

1 2 3 4

DRAINAGE DEDICATION

10' Utility Easement

WICHITA-VALLEY CENTER FLOOD CONTROL

Plan Scale: 1" = 40'
Profile Scale: 1" = 40' Horz.
1" = 5' Vert.

R. KRUG
R. NOWELL

D.R. 282

135
130
125
120
115

Sta 0+20 Line 1
Begin 8" Line at Proposed MH.

Sta 1+92 Line 2
= Sta 6+00 Line 2
Const Std MH
Type 'A' or 'C'

Sta 3+88.5 Line 1
Const Std MH
Type 'A' or 'C'
8" Stub SSW
End Line 1

E. Porter

Proposed Top of Curb 37th St. N.

6" Woodrow

Natural Ground

Prop 12" Water Line

118.69' Out
1130.0 To
12.41' Fr. Prop. Line 1
12.41' Fr. Prop. Line 2

102 Lin Ft of 8" ABS Composite Pipe at 0.9% Grade

284.54 Lin Ft of 8" ABS Composite Pipe at 0.98 % Grade

Sta 0+20 Line 2
Sta 1+92 Line 1
Begin 8" Line 2

Sta 1+92 Line 2
Const Std MH
Type 'A' or 'C'
8" Stub E
8" Stub SE
End Line 2

Natural Ground

Line 2

118.84' Out
12.41' To Prop Line 2
12.41' To Prop Line 1

142 Lin. Ft of 8" ABS composite Pipe at 0.40 % Grade

2

Lat. 30, Main 21, S.S. No. 22
City Of Wichita, Kansas
R. W. Linn City Engineer
Date:
Sheet No. 1 Of 1 Sh.
Proj No. 468 76 245 80528 000 000 001

0 1 2 3 4 5 0 1