B. M. 134.10' "M" in Mueller Fire Plug N.W. cor. 35th and Seneca.

NOTE TO CONTRACTOR:
Contractor is to replace all fences and Septic tank laterals. Also construct temporary fences where necessary.

NOTE:
Do not remove or damage frame shed @ 3656 North Seneca St.

SENECA

WALNUT

STREET

GROVE

PAYNE AVE.

35TH ST.

BENEFIT DISTRICT

Lot 1 Block 1 BESSIE BELLE ADDITION

John L. Eddy 3620 N. Seneca

Ira L. O'Donnell 3834 N. Seneca

Eugene E. McDowell 3836 N. Seneca

C. E. Klag 3866 N. Seneca

Kenneth E. Raddack 3730 N. Seneca

Geneva S. Hendrix 3734 N. Seneca

Harold D. McKay 3798 N. Seneca

Geneva S. Hendrix 3734 N. Seneca

Samuel I. Smith 1402 W. 35th St. N.

Daniel B. Wolfe No. 1, Bethel Court Jackson, New Jersey

Wesley E. Burns 3651 Payne Ave.

Wayne D. Warenfell 3721 Mascot

Sta. 0+00.0 Exist. M.H. Exist. 8" Stub N.

Sta. 3+11.5 Const. Std. M.H. Type "A"

Sta. 6+26.9 Const. Std. M.H. Type "A" Install Stub for property owner.

South line of benefit district.

20' temp. Const. Easement.

10' temp. Const. Easement.

Big Chisholm Creek DITCH diversion

Plan Scale 1" = 40'
Profile Scale 1" = 4' Vert.

Exist'g M.H. Exist'g 10"-8" Stub No.

Identical Manholes

Natural ground

Conc. drives on Seneca St.

Proposed top of E. cb at Seneca St.

This portion of Sanitary Sewer built on Lat. 65, Sub. 4, S. S. No. 23 Project No. C28-10

131.04 N. Rim M.H.

8" Clay Pipe @ 0.20 % 8" Clay Pipe @ 0.20 %

125.40 F/o 8" Stub N.

125.96 F/o Exist. M.H. Exist. 8" Stub No.

123.96 F/o

126.16 126.36 126.56 126.59 F/o 126.74 126.96 127.16 127.21 F/o

621 lin. ft. of 8" Clay Pipe @ 0.20% grade.

0 1 2 3 4 5 6

130 120

LAT. 22, SUBMAIN 4, S. S. NO. 23

CITY OF WICHITA, KANSAS

B. E. SMITH CITY ENGINEER

NOV. 1970 PROJECT NO. C23-74