S. 31, T. 26 S., R. 2 E. of 6th P.M., U.S. Survey
E. 1/4 Sec. M. of Salina A.S. No.

Sta 6+50 Constr. Brick Manhole Type A.

Sta 4+00 Constr. Brick Manhole Type A.

Sta 0+96 Constr. Brick Manhole Type A.

Sta 1+48 Constr. Brick Manhole Type A.

Sta 8+50 Constr. Brick Manhole Type A.

Sta 0+00 Exist. Manhole Wet Well for Pump with 8" Stub North. Begin Proj. at Sta 0+05.

Exist. 8" Vit. C.P. Sewer

Exist. 8" Cast Iron Force Main Sewer

29TH. ST.

SALINA AVE.

TIMMERMEYER GARDENS

WARENFELT ADDITION

Lloyd K. Nuell 1039 N. 69th St. Wichita 4, Ks.

Leonard W. Kelly 3049 Salina Wichita 4, Ks.

Everett F. Nuell 3045 Salina Wichita 4, Ks.

Rose M. Johnson 3041 Salina Wichita 4, Kansas

Mrs. Ida A. Nickel 3015 Salina Wichita 4, Ks.

Wayne J. Warenfelt 3321 Hazel Wichita 4, Ks.

16' Perm. Easement

20' Temp. Easement

8' Perm. Easement

4' Easement

Line No. 1

244.81'

87.73'

87.73'

67.2'

67.2'

131.9'

NOTE TO CONTR.
REMOVAL OF POSTS TO BE INCIDENTAL TO PROJECT.

Profile West Line Salina Avenue

Exist. Ground

Line No. 1

Sta 0+00 Exist. Manhole Wet Well for Pump Station

Conc. Drive El. 1128.63

Sta 0+90.0 Const. Std. N.H. Type "A"

Sta 1+48.0 Const. Std. N.H. Type "A"

Sta 4+00.0 Const. Std. N.H. Type "A"

Conc. Drive El. 1128.64

Conc. Drive El. 1128.96

Sta 6+50.0 Const. Std. N.H. Type "A"

Conc. Garage Floor El. 1128.90

Conc. Drive El. 1128.76

3 Ft. Conc. Walk El. 1128.95

Sta 8+50.0 Const. Std. N.H. Type "A"

130

120

110

96 L.F. 8" V.C.P. @ 0.3%

52 L.F. 8" V.C.P. @ 0.3%

252 L.F. 8" V.C.P. @ 0.3%

250 L.F. 8" V.C.P. @ 0.3%

200 L.F. 8" V.C.P. @ 0.3%

0 Exist. Manhole Wet Well Sta. 0+00 Flow Ln. = 1116.00

0+96 Constr. Manhole Flow Out = 1116.29 In = 1116.39

1+48 Constr. Manhole Flow Out = 1116.35 In = 1116.65

2 Flow = 1116.80

3 Flow = 1117.10

4 Constr. Manhole Flow = 1117.40

5 Flow = 1117.70

6 Flow = 1118.00

6+50 Constr. Manhole Flow = 1118.15

7 Flow = 1118.30

8 Flow = 1118.60

8+50 Constr. Manhole Flow = 1118.75

9 Flow = 1118.90

P. & I. Scale
Profile Scale

LAT. 30, SUBMAIN 4, S. S. NO. 23
CITY OF WICHITA, KANSAS
B. E. SMITH CITY ENGINEER
MAY 1969 PROJECT NO. C23-82
SHEET NO. 1 OF 2

NOTE TO CONTRACTOR:
The contractor is to protect all...

Sta 11+54 Line No. 1 = Sta 0+00 Line No. 2. Constr. Brick M.H. Type A.

Sta 1+00 Line No. 2 Constr. Brick M.H. Type A. End Line.

Sta 8+50 Constr. Brick Manhole Type A.

Sta 12+64 End Line No. 1 and Plug Pipe.

Sta. 18+62.0 Exist. 2" gas line 3.5' deep.

Line No. 1

Line No. 2

12' Perm. Easement

20' Temp. Easement

TIMMERMEYER GARDENS

SALINA AVE.

31ST. ST.

33 34 35

U. L. Macklin 3121 Salina Wichita, Ks.

R. W. Womer 120 Lynwood Blvd. Wichita 4, Ks.

Francis W. Hinkle 3159 Salina Wichita 4, Ks.

Clark A. Cartwright 3513 N. Meridian Wichita 4, Ks.

Note: See Lat. 31, Sub. 4, S.S. No. 23 for continuation of sewer north.

N

Plan Scale 1"=40'
Profile Scale Horz. 1"=40' Vert. 1"=4'

Profile West Line Salina Avenue

Exist. Ground

Sta. 8+50.2 Constr. Brick M.H. Type A.

Conc. Drive El. 122.59

Sta. 11+54.0 Constr. Sta. No. 1 Type A

3 Ft. Conc. Walk El. 122.59

Sta. 18+64.0 End 8" V.C.P. Plug pipe

Sta. 18+62.0 Exist. 8" gas line

Line No. 1

304 L.F. 8" V.C.P. @ 0.3%

110 L.F. 8" V.C.P. @ 0.3%

130

120

110

9+50 Const. Manhole Flow = 1.20

9 Flow = 1.20.90

10 Flow = 1.19.20

11 Flow = 1.17.50

11+54 Const. Manhole Flow = 1.17.66 Flow Line No. 2 West = 1.17.26

12 Flow = 1.19.80

12+64 End Pipe & Plug Flow = 1.19.99

13

Sta 0+00.0 Line No. 2 Sta 11+54 Const. Sta. No. 1 Type A Constr. Brick Manhole

Line No. 2

100 L.F. 8" V.C.P. @ 1.0%

Exist. Ground

Sta. 1+00 Const. Sta. Brick M.H. Type A.

130

120

110

Sta 0+00.0 Line No. 2 = Sta 11+54 Line No. 1 Constr. Manhole Flow = 1.19.66 Flow 8" V.C.P. Line = 1.19.76

1+00 Const. Manhole Flow = 1.20.76 End Line No. 2.

LAT. 30, SUBMAIN 4, S. S. NO. 23
PROJECT NO. C23-82
SHEET NO. 2 OF 2