B. M. 122.66 nail N. S. P. P. S.E. 29th & Woodland.

E. C. & L. R. COLE'S ADDITION TO CAREY PARK

NOTE: Utility contractor to reinstall fence where construction requires temporary removal.

Plan scale 1" = 40'
Profile Scale 1" = 40' Vert.
1" = 4' Hor.

Surveyed by W.W.R. & M.H.D.
Checked by

Sta. 0+00 Const. Std. M.H. Type "A" over Exist. 15" V.C.P.

Sta. 1+66 Const. Std. M.H. Type "A"

WOODLAND

29TH ST.

JEANETTE

Joseph Groves 3028 W. 29th

Ed. Nigel 3010 Woodland

Otha Wright 3016 Woodland

Bessie N. Thomas 3018 Woodland

Richard M. Reynolds 3022 Woodland

Silas G. Smith 3047 Jeanette

Temp. Esmt.

Sta. 2+03.5 Const. Std. M.H. Type "A"

Sta. 4+60 Const. Std. M.H. Type "A"

Sta. 7+00 Const. Std. M.H. Type "A"

Sta. 9+90.0 Const. Std. M.H. Type "A"

Sta. 12+70.0 Const. Std. M.H. Type "A"

30TH ST.

AVE.

31ST ST.

William S. Nevin 3100 Woodland

Paul J. Kelmig 3104 Woodland

Wm. L. Hartman 3120 Woodland

W. R. Bell 3140 Woodland

Wallace 3158 Woodland

Lyman L. Ray 3168 Woodland

Mattie Bills 3101 Jeanette

Lena Smith 3115 Jeanette

Arlene N. Scheles 3119 Jeanette

G. E. Hicks 3132 Woodland

Claude W. Watt 3135 Jeanette

Eva L. Irk 112 W. 18th

Naomi G. Wile 3135 Lagrelle

Hanson Masonic Home 401 S. Seneca

Lynn Ramsey 3100 Arkansas

Note: All Temp. Esmts are 20' From the Perm. Esm't. unless otherwise Noted.

Sta. 0+00 Const. Std. M.H. Type "A"

Sta. 1+66 Const. Std. M.H. Type "A"

Sta. 2+03.5 Const. Std. M.H. Type "A"

Sta. 4+60 Const. Std. M.H. Type "A"

Sta. 7+00 Const. Std. M.H. Type "A"

Sta. 9+90.0 Const. Std. M.H. Type "A"

Sta. 12+70.0 Const. Std. M.H. Type "A"

W. R. Jeanette

E. R. Woodland

Natural Ground

8" V.C.P. +0.2%

8" V.C.P. +0.2%

8" V.C.P. +0.4%

930 Lin. Ft. 8" V.C.P. @ +0.2% Grade

880 Lin. Ft. 8" V.C.P. @ +0.4% Gr.

130

120

0 1 2 3 4 5 6 7 8 9 10 11 12

LAT. 31, SUBMAIN 4, S. S. NO. 23

CITY OF WICHITA, KANSAS

B. E. SMITH CITY ENGINEER

APRIL 1969 PROJECT NO. C23-83

B. E. SMITH 496 REGISTERED PROFESSIONAL ENGINEER KANSAS

L. R. SEIFERT 9614 REGISTERED LAND SURVEYOR KANSAS

3 12 4 (2)