B. M. 213.52 Extreme N.W. cor. flat stone slab on Lambsdale Mon. SW cor. 13th & Parkwood.

B. M. 213.65 Head 60d nail root of 10" Locust tree 5' Lt. of Sta. 0+10

N

REPLAT OF

SPRING ACRES

Harold T. Beck
837 Spring Dr
Wichita 15, Ks.

Sam E. Rudd
54.00 E 13th
Wichita 8, Ks.

S. H. Marcus
1415 Spring Dr.
Wichita 15, Ks.

NOTE: Replace fence.

Sta. 0+00.0 Const. Std. M.H. over ex. 18" S. San. Sewer

Sta. 1+00.0 Const. Std. M.H.

Sta. 2+00.0 Const. Std. M.H.

Sta. 2+70.0 Const. Std. M.H.

Sta. 0+00.0 Exist'g M.H. over ex. 18" S. San. Sewer

Exist'g M.H. 218.5' N. I.E. Flo 210.63

Swimming Pool

House

Natural ground

Exist'g N. ab. of 13th St.

8" V.C.P. @ 1.0 %

2- Std. manholes

270 lin. ft. of 8" V.C.P. at 1.0 % grade

210.93 Flo in exist'g 8"
222.20 Flo in

229.20

224.20

224.90 Flo out

13TH ST.

LANE

SPRING

ALLEY

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 4' Vert.

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

EXTENSION TO
LAT. 30, D. C. S., S. S. NO. 12
CITY OF WICHITA, KANSAS
B. E. SMITH CITY ENGINEER
OCT. 1965, PRIVATE CONTRACT

S. Rim 128.87
Flo 118.74

EWING AVE. Vacated

FORT SCOTT END ADDN.

29TH ST.

Plan Scale 1" = 40'
Profile Scale 1" = 10' Horz.
1" = 1' Vert.

B. M. 127.87 X-cut on S. Rim M.H. north side 29th approx. 40' E. of N. Ent. to bldg. 1515 E. 29th St. E.

B. M. 126.86 R. R. Spike N. Side I. P. on S. E. Cor. 29th St. & Ohio.

Sta. 1+73.2 Remove exist'g O. H. Const. Std. M.H.

Sta. 1+90.0 Const. Std. M.H.

Sta. 0+00.0 Exist'g M.H.

Vacated 8" Clay Ln. Rec.

Bldg. 1515 E. 29th St.

CLEVELAND AVE Vacated

Gate

OHIO AVE.

Sta. 0+00.0 Exist'g M.H.

Sta. 1+90.0 Const. Std. M.H.

Sta. 3+73.2 Remove Exist'g O.H. Const. Std. M.H.

S. Rim M.H. 127.87

Natural ground

Sand Fill & Flush

8" V.C.P. @ 0.8 %

8" V.C.P. @ 0.8 %

121.56

122.86

123.65 Flo out Exist'g O.H.

123.15 Flo ex. 8"

121.98 Flo

121.98

121.48 Flo in 8"

2- Std. manholes
373.2 lin. ft. of 8" V.C.P. at 0.8 % grade
50 lin. ft. of Sand fill or flushing

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

LAT. 50, SUBMAIN 4, S. S. NO. 23
CITY OF WICHITA, KANSAS
B. E. SMITH CITY ENGINEER
OCT. 1965 PRIVATE CONTRACT

W. S. DICKEY CLAY MFG. CO.
BIRMINGHAM ALA. MEXICO, MO. KANSAS CITY, MO.
SAN ANTONIO, TEX. TEXARKANA, TEX.-ARK. ST. LOUIS, MO.

a ii 3 (1)