

B. M. 204.69 Top N. end W. c/vt. Headwall
 Ent. c/vt. N. S. 21st. 200' E. of Edgemoor.

Plan Scale 1" = 40'
 Profile Scale 1" = 40' vert.

Survey by G.Y. Book 237-Y
 Plan by J.R.W.
 Checked by

NOTE:
 Use extreme caution in
 excavating stub at Sta.
 0+00.0 as end of pipe
 may be farther east of
 manhole than indicated
 by plan.

Sta. 0+00.0
 Exist. M.H.
 Exist. 8" stub East

5+47.8
 Sta. 5+50.0
 Const. Std. M.H.
 Type "A" or "C"
 Install 8" stub NW & SE.

2+33.5
 Sta. 5+00.0
 Const. Std. M.H.
 Type "A" or "C"

Sta. 5+50.0
 Const. Std. M.H.
 Type "A" or "C"
 Install 4" stub NW & SE.

Sta. 0+00.0 Exist. M.H.
 Exist. 8" stub East

Sta. 5+00.0
 Const. Std. M.H.
 Type "A" or "C"

18' to Water table
 6-27-75
 util.

N. Rim M.H.
 208.11

Lot 13
 Basement Floor
 Lot 1
 Basement Floor

Proposed So. ab.
 Shadybrook Ln.

Existing N. ab.
 20th St.

Natural ground

Proposed N. ab.
 Malcolm St.

545 Lin. ft. of 8" Clay Pipe @ 0.40 % grade

As Built 10-14-75
 LAT. 12, SUBMAIN 5, S. S. NO. 23
 CITY OF WICHITA, KANSAS
 R. W. LINN — CITY ENGINEER
 DATE: PROJECT NO. DBKL566041

