



B. M. 218.21 "D" in Mid Kansas
 N.L. 21st. E. of Oliver.

Survey by Mr. B. R. Ark 45
 Checked by _____

Plan Scale 1" = 40'
 Profile Scale 1" = 40' Vert

NOTE:
 The removing or plugging
 of the exist. 8" stub south
 at Sta. 0100.0 is to be
 incidental to the project.

Sta. 0198.0 Const.
 Std. M. H. Type "A"

Sta. 0100.0
 Exist. M. H.
 Remove or Plug
 Exist. Stub S.

Sta. 5119.4 Const.
 Std. M. H. Type "A"
 Install Stub S. for Bldg.

Sta. 3110.0 Const.
 Std. M. H. Type "A"

Sta. 7130.0 Const.
 Std. M. H. Type "A"
 Install Stub S.W. for Bldg.

Sta. 0100.0 Exist. M. H.
 Remove or Plug
 Exist. Stub South
 Water Line.

Sta. 0198.0 Const.
 Std. M. H. Type "A"

Sta. 3110.0 Const.
 Std. M. H. Type "A"

Sta. 5119.4 Const.
 Std. M. H. Type "A"
 Install Stub S. for Bldg.

Sta. 7130.0 Const.
 Std. M. H. Type "A"
 Install Stub S.W. for Bldg.

S. Rim M. H.
 223.84

Exist. E. of
 Oliver St.

130 Lin. ft. of 8" V.C.P. @ 0.40% grade.

LAT. 27, SUBMAIN 5, S. S. NO. 23
 CITY OF WICHITA, KANSAS
 B. E. SMITH CITY ENGINEER
 FEB. 1969 PROJECT NO. C28-103