FINAL SURVEY	SURVEYED	DATE
	DRAWN	
	TRACED	
	CHECKED	
NOTE BOOK	AREA CHECKED	
NO.		

Sta 0+00 Construct M.H #1 Top Elev = 1273.5

℄ 33' Drainage Easement

℄ 10' Utility Easement

Exist M.H.

Sta 2+41.6 Construct M.H #3. Defl = 38°23' Rt

Sta 1+244 Construct M.H #2. Defl = 62°10'30" Lt

℄ E 45TH STREET SOUTH

℄ CLARENCE AVE

Sta 4+82.0 Construct M.H #4 Defl = 14° 11' Rt

Remove exist. Pump House down to top of tank & fill tank w/sand - By Owner

Sta 6+49.6 Construct M.H #5 connect to exist 6" P.V.C.

Connect exist 4" waste to new 6" P.V.C.

Install 4" P.V.C. from exist. waste

N

1" = 50'

B.M. #1 S. edge M.H. ring 9' West M.H. - 9.5' N. of M.H. #1 Elev = 1273.75 Pavement Elev = 1266.52

B.M. #2 S.E. Cor. conc. slab septic tank cover. Elev = 1278.02

CITY OF WICHITA

APPROVED: Approval does not relieve th... from any responsibility for ... deviations from the contrac... ments or for any deficiencies of equipment, work, or materials.

Date 6/14/66

Engineering Div. [signature]

Note:
The Gas Service Company records show a 2" steel Main - parallel to & 10'W of the E line of Clarence Ave.

The City of Wichita Water Department shows a 12" S.I.P. ~~Main~~ in Clarence Ave.

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

SANITARY SEWER
FAUNA ELEMENTARY SCHOOL
FOR
BOARD OF EDUCATION

K.D TAYLOR PE
OCT. 1965

ORIGINAL SURVEY	SURVEYED	DATE
	DRAWN	
	TRACED	
	CHECKED	
NOTE BOOK	AREA CHECKED	
NO.		

1275
1270
1265
1280
1275
1270

FORM 4—CROSS SECTION O.P.R. 3 x 5 STANDARD
THE FREDERICK POST CO. CHICAGO