B. M. 80.99 S.W. cor bottom step S. side Wm Allen White School Ent. N.E. 51st. So. & Kansas.

WALLACE ADDN.

3

4

5

DRIVE

GROVE

AVE.

Proposed Sub line

Exist. pavement

POPLAR

Exist. 8" V.C.P.

STA. 0175 CONST. STD. M.H. TYPE "A" INSTALL 4" STUB S.

NOTE: Do not disturb tree.

STA. 0100 EXIST. M.H. REMOVE EXIST. 8" STUB BEGIN PROJECT

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

Plan Scale 1"=20'
Profile Scale 1"=20' Hor.
1"=4' Vert.

T.B.M. 95.60 Top S. cb. Poplar @ W. and exist. pavt. E.L. Wallace Addn.
B.M. 95.70 W. Rim M.H. Sta. 0+00

STA. 0100 EXIST. M.H. REMOVE EXIST. 8" STUB BEGIN PROJECT

STA. 0175 CONST. STD. M.H. TYPE "A" INSTALL 4" STUB S.

Natural Ground

Set top M.H. @ 95.70

Prop. Pvt. Elev.

8" V.C.P. @ 0.20%

Exist. 8" stub in 91.82

75 LIN. FT. 8" V.C.P. @ 0.20% GRADE

3-15-71
Deleted from Plan
JDU
Jr. 76

2ND EXTENSION TO
LAT. 19, DIST. A.S., S.S. #12
CITY OF WICHITA, KANSAS
B.E. SMITH, CITY ENGINEER
PRIVATE PROJECT

Exist'g 8" San. Sewer

3.0'

60'

70'

86.15'

AVE.

942.10'

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

134.84'

134.8'

196.32'

R=50

78.66'

3.1'

8.5'

1'

20'

4" H. P. gas line

4" Water Service line

6" water main

FIFTY FIRST

Exist'g Pavement 28' C.B. & G.C.

ST SO.

8'

94.85'

150'

131.15'

Sta. 3100.0 Const. Std. M.H. Type "A" Install Stub No. For property owner.

Exist'g 8" San. Sewer

Co. Walk

Conc. Walk

4" Gas Line

Sta. 0100.0 Const. Std. M.H. Type "A" over Exist'g 8" S. S.

KANSAS

60'

NOTE: Replace Pavement and Conc. walks.

Derby Oil Co. Property

150'

160'

HYDRAULIC

AVE.

Survey by C.N.Y. on 2-20-Y
Checked by C.N.Y.
Elevations on U.S.C.&G.S. datum

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 4' Vert.

Sta. 0100.0 Const. Std. M.H. Type "A" over exist'g 8" San. Sewer.

CAUTION 8" V.C.P. Water Service line

Natural ground

Sand Fill or Flush

8" V. C. P. 20 0.20 %

Sta. 3100 Const. Std. M.H. Type "A" Install Stub No. for Property owner

2545 Flo in 8" 25.55 Flo in 8"

75.15

75.95

76.15 Flo

300 lin. ft. of 8" V.C.P. @ 0.20% grade.
300 lin. ft. of Sand fill or Flushing.

DERBY OIL COMPANY
SANITARY SEWER
N.E. HYDRAULIC and 51ST. ST. SO.
CITY OF WICHITA KANSAS
B. E. SMITH CITY ENGINEER
AUG. 1968 PRIVATE CONTRACT