Bench Mark: City Standard Disc, 44' S. of ℄ Central and 39' E. of Quarter Section Corner and 19' E. of Center West Parkway
Elev. = 1672.28 City Datum

STATION 0+00 CONSTRUCT STD TYPE 'B' MANHOLE OVER EXISTG LINE

SAW JOINT - REMOVE & REPLACE ASPHALT PAVEMENT AS NECESSARY SEE DETAIL SPECS FOR PAVEMENT REPLACEMENT.

CONSTR. TWO RETAINING WALLS SEE DETAILS

STA. 1+20 END PIPE CONSTRUCTION

LINDEN DRIVE

CENTRAL AVENUE

MH RIM EL. 1672.02 TYP
Pipe In = 1160.66

Private 6" San. Sewer

Private 6" Utility Easmt

House

## FOREST HILLS ADDITION

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will prepay the City of Wichita for all fees of inspection.

10-18-84

APPROVED AS NOTED
By CITY ENGINEER OF WICHITA
See note on 1/28 plan
Sanitary Sewers
Storm Sewers
Driveway Approaches

NOTE NO. 1 - WORK SHOWN ON THIS PLAN HAS BEEN REVIEWED FOR LOCATION AND CONFORMANCE TO APPLICABLE ADOPTED CITY STANDARDS ONLY.

SCALE 1" = 40' HORIZ
1" = 5' VERT

Trench with Asphalt Emulsion (ESSHT)

2" of Asphaltic Concrete meeting City Spec.

Existing Bituminous Pvt.

Base Course to be 2" thicker than existing and of the material meeting City specs.

6" Layers of earth free from large clods & stones Compacted by mechanical tampers or vibrating tampers

95% SM Comp.

95% SM Comp.

Varies

Curb wall

SEWER PIPE

PIPE BEDDING

O.D. of Pipe + 16"

Standard Trench Back, as described in the latest edition of ASTM D-2321, shall be performed to verify the sewer requirements for the Department of the Dept. of Engineering or the Dept. of Operations and Maintenance. Any spring rock shall be included in the unit price bid for the 2321 23 item.

PAVEMENT REPLACEMENT DETAIL

NOTE: PIPE CROSSING TO BE SUPPORTED BY THE RETAINING WALL STRUCTURES "SEE DETAIL"

CONTRACTOR TO PROTECT EXISTING CREEK BANK AS MUCH AS POSSIBLE DURING THE CONSTRUCTION & VEGETATION ON THE RETAINING WALLS TO PREVENT ANY EROSION.

20 LF 6" Ductile Iron Pipe. Contractor shall be responsible for obtaining approval of pipe joint deflection in units or degrees and equal lengths.

155
150
145
140

0
1 +20

PLAN

PIPE JOINT

SECTION

DETAIL CONCRETE RETAINING WALL

Note: Contractor to contact K.C.C. Oil & Gas Pipeline for approximate utility locations which may be on the west side of Linden Drive prior to beginning of any construction work project.
Pipe joints shall be installed to where the joint falls on the corner of the retaining wall structure.
Contractor shall contact Grace (Jackson) 264-4400 of City of Wichita to sign a contract for inspection services and seek permit for any construction proceeding.

NORBERT WOOTEN
LICENSED
8476
KANSAS
PROFESSIONAL ENGINEER

OCTOBER 1984

PRIVATE SANITARY SEWER TO SERVE PART OF LOT 1, BLK 1, FOREST HILLS ADDITION

PROJECT NO. 468-78-245-80000-000-000-008

CITY OF WICHITA, KS

BAUGHMAN COMPANY, P.A.
SURVEYING & ENGINEERING
316/262-2171 • 330 LAURA • WICHITA, KANSAS 67211

PLATE I - PLAN - PROFILE - F.A.B.
CLEARPRINT PAPER CO., S.F. CAL.
NO. 1000H-1

FILMED FROM THE BEST AVAILABLE COPY