Sta. 0+00 - Connect to Exist. MH

Remove Exist. Well

LOT 2 - VARIANT ADD.

Asphalt Parking Lot

Sta. 3+40 - Const. Std. Type "A" or "C" MH

DAYLIGHTS (From Surf.)

4" PVC

128'

TRANSFORMER

10'

10'

0.5'

R

W

Watermeter

Scale: 1" = 20'

89°32'

6"S

20' Easement

6"S

91°26'

CHECK WITH KG&E ON EXACT LOCATION PRIOR TO LAYING PIPE

℄ Conc. Drive

℄ Conc. Drive

30'

Joint Ingress & Egress Esmt.

200'

Remove & Replace 11 S.Y. Exist. Conc. Drive Pvmt.

Building

LOT 2 - JENKINS FIFTH ADD.

7.5

12.5'

20' Easement

20' Easement

Exist. 8" VCP San. Sewer

6135 Building

C 5/8/9

10-16-75

Sta. 4+89 - Const. Std. Type "A" or "C" MH

JENKINS FIFTH ADD.

200'

Lot Split Line

Install 6" Stub

95°

LOT

8-11-75

D.E.S.

B.M. - Rim of Exist. MH @ Sta. 0+00 - Elev. 114.16

Sta. 0+00 - Connect to Exist. MH

Exist. Ground

Sta. 3+40 - Const. Std. Type "A" or "C" MH Top Elev. 117.5

Sta. 4+89 - Const. Std. Type "A" or "C" MH Top Elev. 119.0

340 L.F. 8" V.C.P. @ +1.40%

149 L.F. 8" V.C.P. @ +1.40%

Install 6" Stub

CITY PROJECT NO. DBKW 705022

LOT 1 - JENKINS FIFTH ADD.