


NOTE:
Concrete Tops to be installed on thin mortar cushion to insure full support along brick walls. Concrete tops may be cast in place or precast. Concrete used for inlet construction shall be concrete pavement mix with air entrainment.



***NOTE: Slope of Inlet tops to Match Sidewalk or Parking Slopes within Limits Indicated.



Weight = 180 Lbs.

**See City of Wichita Standard Manhole Ring and Cover Detail Sheet for Cover Details to Be Used With Inlet Frame.*



The ends of all pipes installed in inlets shall be cut off flush with the inside face of the inlet wall



* Field Bend or Cut Reinforcing as Required for Clearance.
 ① 4 (Hl - 12") (Hl - 21") Rounded down to nearest 0.5'
 ② Hl - 3"

STANDARD CURB INLET PRECAST TOPS			
W	PRE-CAST TOP SIZE	PIPE SIZE	CU. YD. CONC.
4'-4"	3'-8" x 6'-4" x 1 1/2"	21" & SMALLER	0.38*
5'-4"	4'-0" x 6'-4" x 1 1/2"	24" & 30"	0.51*
6'-4"	5'-0" x 6'-4" x 1 1/2"	36" & 42"	0.64*
7'-4"	6'-0" x 6'-4" x 1 1/2"	48" & 54"	0.77*
8'-4"	7'-0" x 6'-4" x 1 1/2"	60" & 66"	0.90*



STANDARD TYPE 1-A
CURB INLET
OPENING = 6" x 5'-0"

CITY ENGINEER
ARMOUR, P.E., L.S.

PROJECT NUMBER	XXXX PPS
----------------	----------

CITY ENGINEER'S OFFICE
CITY HALL - SEVENTH FLOOR
455 NORTH MAIN STREET
WICHITA, KANSAS 67202-1620
(316) 268-4501
(316) 268-4114 FAX

DESIGN	DRAWN
COW	COW

SHEET
4 OF 5