

TOBEN

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	39.19	15.60	79.37	26.33	79.37	26.33
0+50	46.53	12.84	93.50	19.14	172.87	45.47
1+00	54.45	7.83	113.27	11.70	286.14	57.17
1+50	67.88	4.80	16.28	1.09	302.42	58.26
1+56.39	69.68	4.45	121.84	5.43	424.26	63.69
2+00	79.53	2.87	156.08	4.15	580.31	67.85
2+50	86.97	2.02	166.43	3.05	746.74	70.89
3+00	90.57	1.57	110.41	1.85	857.15	72.74
3+32.89	103.91	0.00	60.33	1.24	917.48	73.99
3+50	86.51	1.96	66.21	1.59	979.46	75.57
3+70.96	82.18	2.50	0.00	0.00	979.46	75.57

DRIVE

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+32.92	26.28	0.00	16.34	0.00	16.34	0.00
0+50	25.45	0.01	4.67	0.00	21.01	0.01
0+54.98	25.45	0.02	43.87	0.01	64.88	0.02
1+00	27.17	0.00	51.40	0.00	116.28	0.02
1+50	28.35	0.00	16.80	0.00	133.08	0.02
1+66.10	28.01	0.00	0.00	0.00	133.08	0.02

EARTHWORK SUMMARY

PAVING	STREET	CUT CU. YDS.	LOOSE FILL CU. YDS.
	TOBEN	979.5	75.6
	DRIVE	133.1	0.0
	TOTAL	1,112.6	75.6
	15% SHRINKAGE STREETS TOTAL	1,112.6	11.3 86.9

FINAL

Designed By: T. Austin/S. Schmidt
Drawn By: S. Schmidt
Poe Job No.: 1831A
Date: June, 2005



POE & ASSOCIATES, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/683-4114 ■ FAX 316/683-4444

MEDITERRANEAN PLAZA ADDITION
PRIVATE STREET IMPROVEMENTS
EARTHWORK SUMMARY
CITY OF WICHITA, KANSAS
JAMES ARMOUR, P.E. - CITY ENGINEER
167 PPP (607879)

Revised

Approved

By

Date

No.