STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+40.90	38.47	0.00				
2+00	19.87	0.00	63.86	0.00	63.86	0.00
2+50	29.49	0.00	45.70	0.00	109.56	0.00
3+00	18.14	0.00	44.09	0.00	153.65	0.00
3+50	26.06	0.00	40.93	0.00	194.58	0.00
4+00	21.25	0.10	43.81	0.09	238.39	0.09
4+50	15.35	2.59	33.89	2.49	272.28	2.59
5+00	15.54	0.00	28.60	2.40	300.88	4.99
5+50	21.95	0.00	34.71	0.00	335.59	4.99
6+00	21.38	0.00	40.12	0.00	375.71	4.99
6+50	24.81	0.00	42.77	0.00	418.48	4.99
7+00	32.64	0.00	53.20	0.00	471.68	4.99
7+50	31.59	0.00	59.47	0.00	531.15	4.99
8+00	24.53	0.00	51.96	0.00	583.11	4.99
8+50	14.34	0.00	35.99	0.00	619.11	4.99
9+00	11.96	0.01	24.35	0.01	643.46	5.00
9+50	9.37	0.05	19.75	0.05	663.21	5.05
10+00	4.99	1.27	13.30	1.22	676.52	6.27
10+50	2.08	2.85	6.55	3.82	683.07	10.09
11+00	5.51	1.90	7.03	4.40	690.09	14.49
11+50	7.29	1.62	11.85	3.26	701.95	17.74
12+00	25.50	0.05	30.37	1.55	732.31	19.29
12+50	29.35	0.00	50.79	0.05	783.10	19.34
13+00	36.84	0.00	61.28	0.00	844.39	19.34
13+50	35.76	0.00	67.22	0.00	911.61	19.34
14+00	26.71	0.00	57.84	0.00	969.45	19.34
14+50	9.25	0.00	33.30	0.00	1002.75	19.34
15+00	14.89	0.03	22.35	0.03	1025.10	19.37
15+50	16.17	0.14	28.76	0.16	1053.86	19.53
16+00	22.36	0.00	35.68	0.13	1089.53	19.66
16+50	38.53	0.00	56.38	0.00	1145.92	19.66
17+00	30.54	0.00	63.96	0.00	1209.87	19.66
17+50	16.49	0.52	43.55	0.48	1253.43	20.14
18+00	8.57	1.63	23.21	1.99	1276.64	22.13
18+50	3.38	2.92	11.07	4.21	1287.70	26.34
19+00	4.56	0.86	7.36	3.50	1295.06	29.84
19+50	13.62	0.00	16.83	0.80	1311.89	30.64
20+00	17.63	0.00	28.94	0.00	1340.83	30.64
20+50	26.04	0.00	40.44	0.00	1381.26	30.64
21+00	19.59	0.00	42.25	0.00	1423.51	30.64
21+50	12.99	0.00	30.17	0.00	1453.68	30.64
22+00	6.70	0.00	18.23	0.00	1471.90	30.64
22+50	21.01	0.00	25.66	0.00	1497.56	30.64
23+00	27.77	0.00	45.17	0.00	1542.73	30.64
23+50	27.22	0.00	50.92	0.00	1593.65	30.64
24+00	25.41	0.00	48.73	0.00	1642.38	30.64
24+20.82	24.97	0.00	19.42	0.00	1661.80	30.64
24+50	19.45	0.00	23.93	0.00	1685.73	30.64
25+00	17.06	0.00	33.50	0.00	1719.23	30.64
25+50	20.74	0.09	34.68	0.08	1753.91	30.72
26+00	10.53	0.41	28.87	0.46	1782.78	31.17
26+50	13.91	1.00	22.69	1.27	1805.47	32.45
27+00	8.67	1.59	20.75	2.39	1826.22	34.84
27+50	11.49	1.73	18.40	3.14	1844.62	37.98
27+79.47	13.77	1.73	13.63	1.93	1858.25	39.91
28+00	16.12	2.15	11.37	1.47	1869.62	41.39
28+50	21.78	0.00	35.09	1.99	1904.71	43.37
29+00	15.74	0.05	34.74	0.05	1939.45	43.42
29+42.25	16.99	0.01	25.61	0.05	1965.06	43.47
30+00	6.39	4.97	24.83	5.47	1989.89	48.94
30+50	4.06	5.92	9.59	10.30	1999.48	59.24
31+00	4.04	3.53	7.37	8.92	2006.84	68.16
31+50	8.22	2.93	11.09	6.14	2017.94	74.30
32+00	12.25	2.12	18.80	4.82	2036.74	79.12
32+29.40	5.63	5.30	9.66	4.18	2046.40	83.30
32+50	9.66	4.25	5.83	3.64	2052.23	86.94
33+00	14.18	3.29	22.07	6.98	2074.30	93.92
33+50	12.67	2.41	24.86	5.27	2099.16	99.20
34+00	18.90	0.89	29.24	3.05	2128.40	102.25
34+50	30.25	0.57	45.51	1.35	2173.91	103.60
			0.00	0.00	2173.91	103.60

Note: Earthwork Quantities listed reflect the existing ground at the time of the survey. Quantities have been calculated using the average End area method. No factors for soil expansion, loss, or compaction have been figured into these Quantities.

Drawing File: E:\Edgewater_45th Street Improvement\Land\dwg\base.dwg

OCTOBER, 2008

Design: TCA
Drawn: TCA
Approved: JFB
Scale: 1:20

Project No. 0808-E183 CAPITAL IMPROVEMENT PROJECT

Cross Sections

45TH STR. PAVING RIDGE RD TO CIMARRON STR.

Baughman Company , P.A.
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
Baughman ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

SHEET 25 OF 25