



*Note: All Pavement Marking shall be Thermoplastic, Install per manufactures recommendations and Shall meet KDOT's 2007 Standard Specifications.

Note: Existing Gravel Road Surface Graded from Project or Crushed Rock Base Material shall be used for Shoulder Construction. To be Paid as 2 ft. Compacted Gravel Shoulder (Lin. Ft.).

FABRIC BASE REINFORCEMENT SHALL BE B X 1100 BY TENSAR CORPORATION OR APPROVED EQUAL. FABRIC BASE REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

Drawing File: E:\Edgewater_45th Street Improvement\Details\TypSec.dwg

Design: TCA
Drawn: TCA
Approved: JFB
Scale: NO SCALE

Project No. 08-08-ET83 CAPITAL IMPROVEMENT PROJECT

Typical Section

45th St. N CIMARRON STREET to HOOVER STREET

Baughman Company, P.A.
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

OCTOBER, 2008

SHEET 3 OF 19