BENCH MARK:
City Standard Brass Cap
NE corner bridge Pawnee & Gypsum Creek.
Elev. 123.06

℄ Proposed Gypsum Creek Channel

20'

1:1

15'

3:1

2.5:1

EXISTING SEWER SIPHON 24" & 30" PIPE

EXISTING 42" WIS

PROPOSED 30" SWS

R/W LIMITS

℄ PAWNEE

DWS+3' 120.5

42" WIS

IE. 102.7

103.2

26"

33"

℄ Proposed Channel

℄ Manhole 2+25

IE. Out 103.4
IE. In 103.8

Begin New 30" RCP
IE. Existing 30" RCP 110.5

Existing Manhole
IE. Out 111.1

120
115
110
105
100

300
200
100
0

CITY-COUNTY FLOOD CONTROL OFFICE

PLAN AND PROFILE
PROPOSED
30" SWS
GYPSUM CREEK STA. 278+90

SCALE: 1"= 20' HORIZONTAL
1"= 5' VERTICAL
DATE : 10 FEB 72
DRAWN: CBS

FLOOD CONTROL SUPERINTENDENT