



Sta. 5+85.01, 55.61' Lt. Install  
12' Wide Access Gate  
See Sh. No. 9, 27, & 28

Sta. 5+80.82 to Sta. 10+40.00 Install  
475 L.F. 6' Chain Link Fence  
Remove Existing Fence and Posts  
See Sh. No. 27 & 28

Sta. 10+40.00 to Sta. 12+10.00 Install  
179 L.F. 6' Chain Link Fence (Special)  
See Sh. No. 16, 27, & 28

Sta. 12+08.14, 75.17' Lt. Install  
12' Wide Access Gate  
See Sh. No. 9, 27, & 28

Sta. 12+10.00 to Sta. 16+70.00 Install  
507 L.F. 6' Chain Link Fence  
See Sh. No. 27 & 28

Sta. 4+84.23 to Sta. 8+16.13 Install  
329 L.F. 6' Chain Link Fence  
Remove Existing Fence and Posts  
See Sh. No. 9, 27, & 28

Install 6' Chain Link Fence  
See Sh. No. 9, 27, & 28

STA. 10+00 BEGIN  
Channel Improvements

**LEGEND**

- \*\*\*\* Exist. Elevation
- \*\*\*\* Prop. Elevation
- Prop. Fence
- X Tree Removal
- \*\* Connect Existing Fence to New Post (Subsidiary)

Note: See Cross-sections for Ditch Flow Lines.

CITY OF WICHITA  
JAMES ARMOUR, P.E., CITY ENGINEER  
GYPSUM CREEK  
CONTOUR MAP  
& FENCING PLAN  
CITY OF WICHITA PROJECT NO. 468-82473



K:\32158A\CADD\SHEETS\DRAINAGE\03 Cml.dgn  
 SURV. JG, CP, PLOT CADD DES. DR. TR. CKD. APP.