

NEW JERSEY

Total Volume Table						
Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
8+95.56	0.65	14.29	0.00	0.00	0.00	0.00
9+50.00	5.00	6.40	5.89	20.86	5.89	20.86
9+75.00	4.13	3.25	4.22	4.47	10.12	25.32
10+00.00	0.87	8.63	2.32	5.50	12.43	30.82
10+50.00	1.43	13.01	2.14	20.04	14.57	50.86
11+00.00	7.46	6.90	8.23	18.44	22.80	69.30
11+25.00	8.29	5.98	7.29	5.97	30.09	75.27
11+50.00	1.40	14.82	4.48	9.63	34.58	84.90
11+75.00	0.63	18.90	0.94	15.61	35.52	100.51
12+00.00	0.35	18.15	0.46	17.15	35.97	117.66
12+25.00	0.38	19.95	0.34	17.64	36.31	135.29
12+50.00	0.55	20.66	0.43	18.80	36.74	154.10
13+00.00	1.23	24.93	1.65	42.22	38.39	196.31
13+25.00	0.75	22.81	0.92	22.11	39.31	218.42
13+50.00	1.66	24.65	1.12	21.98	40.43	240.40
13+75.00	0.79	28.68	1.13	24.69	41.56	265.09
14+00.00	0.00	29.41	0.37	26.89	41.93	291.98
14+25.00	0.00	21.48	0.00	23.56	41.93	315.54
14+50.00	0.04	18.17	0.02	18.36	41.95	333.90
14+75.00	14.43	5.56	6.70	10.99	48.65	344.88

Total Volume Table						
Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
15+00.00	17.36	13.86	14.71	8.99	63.36	353.87
15+25.00	0.00	30.88	8.04	20.71	71.40	374.59
15+50.00	0.00	29.38	0.00	27.90	71.40	402.49
16+00.00	0.00	23.55	0.00	49.02	71.40	451.50
16+25.00	0.00	19.72	0.00	20.03	71.40	471.54
16+50.00	0.00	20.93	0.00	18.82	71.40	490.36
16+75.00	0.00	16.00	0.00	17.10	71.40	507.46
17+00.00	0.00	17.80	0.00	15.65	71.40	523.11
17+25.00	0.00	32.99	0.00	23.52	71.40	546.62
17+50.00	0.00	32.38	0.00	30.26	71.40	576.89
18+00.00	0.44	32.29	0.40	59.88	71.80	636.77
18+25.00	0.00	29.45	0.40	57.17	72.20	693.93
18+50.00	1.27	28.58	0.59	26.87	72.79	720.80
18+90.57	0.00	0.00	0.37	8.24	73.16	729.04

BUNKER HILL

Total Volume Table						
Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
50+32.94	0.00	1.10	0.00	0.00	0.00	0.00
50+50.00	9.47	1.93	2.99	0.96	2.99	0.96
50+75.00	18.64	3.80	13.01	2.65	16.01	3.61
51+00.00	13.43	5.92	14.85	4.50	30.85	8.11
51+50.00	22.43	30.21	33.20	33.45	64.06	41.55
52+00.00	27.13	39.27	45.89	64.33	109.95	105.89
52+50.00	42.02	30.81	64.03	64.89	173.99	170.78
53+00.00	55.90	31.19	90.67	57.41	264.66	228.19
53+50.00	78.03	50.83	124.01	75.95	388.66	304.13
54+00.00	66.16	31.17	133.51	75.93	522.18	380.06
54+50.00	50.14	30.23	107.69	56.85	629.87	436.91
55+00.00	37.15	13.63	80.83	40.61	710.70	477.51
55+50.00	10.47	14.03	44.09	25.61	754.79	503.12
56+00.00	34.73	26.51	41.85	37.54	796.64	540.66
56+50.00	23.43	40.42	53.85	61.98	850.49	602.64
57+00.00	21.61	50.81	41.70	84.48	892.19	687.11
57+50.00	1.65	65.96	21.53	106.12	913.72	795.23
58+00.00	11.45	62.69	12.12	119.12	925.85	914.35
58+50.00	22.49	59.00	31.42	112.68	957.27	1027.03
59+00.00	36.08	53.91	54.23	104.55	1011.50	1131.58

Total Volume Table						
Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
59+50.00	22.88	52.03	54.59	98.10	1066.09	1229.67
60+00.00	34.90	34.80	53.50	80.40	1119.59	1310.08
60+50.00	0.41	35.72	32.69	65.30	1152.28	1375.37
61+00.00	6.54	23.96	6.43	55.26	1158.72	1430.63

SOUTH BUNKER HILL

Total Volume Table						
Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
70+50.00	50.67	21.01	0.00	0.00	0.00	0.00
70+62.55	44.83	17.45	22.20	8.94	22.20	8.94
70+75.00	41.43	16.81	19.89	7.90	42.08	16.84
70+80.00	41.86	16.45	7.71	3.08	49.80	19.92
71+00.00	53.22	18.50	35.22	12.95	85.01	32.86
71+20.00	57.84	18.67	41.13	13.77	126.14	46.63
71+25.00	55.71	19.44	10.52	3.53	136.66	50.16
71+30.00	51.19	15.49	9.90	3.24	146.56	53.40
71+50.00	51.54	13.21	38.05	10.63	184.61	64.02
71+60.00	4.00	16.13	10.29	5.43	194.89	69.46
71+70.00	0.04	33.03	0.75	9.11	195.64	78.56
71+75.00	0.07	34.10	0.01	6.21	195.65	84.78
72+00.00	43.77	23.29	20.30	26.57	215.95	111.35
72+22.66	6.31	24.66	21.01	20.12	236.96	131.47

Total Volume Table						
Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
70+80.00	41.86	16.45	7.71	3.08	49.80	19.92
71+00.00	53.22	18.50	35.22	12.95	85.01	32.86
71+20.00	57.84	18.67	41.13	13.77	126.14	46.63
71+25.00	55.71	19.44	10.52	3.53	136.66	50.16
71+30.00	51.19	15.49	9.90	3.24	146.56	53.40
71+50.00	51.54	13.21	38.05	10.63	184.61	64.02
71+60.00	4.00	16.13	10.29	5.43	194.89	69.46
71+70.00	0.04	33.03	0.75	9.11	195.64	78.56
71+75.00	0.07	34.10	0.01	6.21	195.65	84.78
72+00.00	43.77	23.29	20.30	26.57	215.95	111.35
72+22.66	6.31	24.66	21.01	20.12	236.96	131.47

