



The Striping Contractor may be Required to Adjust the Proposed Pavement Marking to Match the Ex. Pavement Markings in the Field. The Contractor may also be Required to Remove & Replace the Ex. Pavement Markings as Necessary, Including Those Removed for Traffic Control Beyond the Construction Limits. These Costs Shall be **INCIDENTAL** to the Lump Sum Bid Item "Pavement Marking".

GENERAL NOTES - MARKING

1. All pavement markings shall conform to the current standards set forth in the latest publication of the "Manual on Uniform Traffic Control Devices".
2. All pavement markings shall be thermoplastic, unless otherwise approved by the Engineer. Pavement markings shall be installed per manufacturer's recommendations and shall meet KDOT's 2007 Standard Specification. Full traffic may not be restored (and substantial project completion achieved) until all pavement markings are in place. Should construction timing be such that restoration of traffic becomes necessary during temperatures prohibiting the installation of thermoplastic markings, the contractor shall install and maintain temporary markings until such time that thermoplastic markings may be properly installed. Except for the material requirement, temporary pavement markings shall be placed equivalent, in every manner (i.e. dimension, frequency, spacing, etc.), to the permanent marking layout. The cost for temporary pavement markings will not be paid for directly, but shall be considered **SUBSIDIARY** to the bid item "Pavement Markings".

BILL OF MATERIALS

ITEMS	UNITS	TOTAL	USE*
PLASTIC MARKING TAPE (4" WHITE)	LF	970	999
PLASTIC MARKING TAPE (6" WHITE)	LF	5405	5568
PLASTIC MARKING TAPE (24" WHITE)	LF	559	576
PLASTIC MARKING TAPE (4" YELLOW)	LF	21,442	22,086
PLASTIC MARKING SYMBOL (LT TURN ARROW) WHITE	EA	34	34
PLASTIC MARKING SYMBOL (RT TURN ARROW) WHITE	EA	2	2
PLASTIC MARKING TAPE (24" WHITE)	EA	2	2
FOR INFORMATION ONLY			

* ±3% Overage

Drawing File: E:\eng\Meridian-47th to 31st\Traffic\Marking.dwg (Marking 06)

Design: TPV
Drawn: TPV
Approved: TPV
Scale: NOTED

Project No. 0510E396 CAPITAL IMPROVEMENT PROJECT
MERIDIAN AVENUE
MARKING AND SIGNING PLAN
MERIDIAN AVENUE - 47TH STREET SOUTH TO 31ST STREET SOUTH

Baughman Company, P.A.
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

September 2009
SHEET 120 OF 187