FHWA REG. NO.	STATE	PROJECT NO.	YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87 N-0502-01	2009	WL12	W226
A.R.R.A-N05(201)					

GRAPHIC SCALE
20 0 10 20 40
(IN FEET)
1 INCH = 20 FT.

MAIZE AVENUE INC.

℄ Maize Avenue = Section Line

Utility Easement

Existing R/W

WATER WELL

landscape area

sidewalk

WL Sta. 247+90.52, 13.99' Lt. =
Maize Rd. Sta. 55+75.33, 40.52' Rt.
Adjust Top Valve Box (8" & 2")
Top Valve Box Elev.=1324.07
N=24760.468, E=51414.221

WL Sta. 248+86.62 = Maize Rd.
Sta. 56+23.18, 35.70' Rt.
Air Release Valve (AR#18356)
Adjust Top Air Release Valve Box Top
Top Valve Box Elev.=1323.60
N=24808.406, E=51408.65

Sta. 57+50.00 END CONSTRUCTION
PROJECT NO. 87 N-0502-01

MAIZE ROAD

54+00 55+00 56+00 57+00 58+00 59+00 60+00

Caution !!
Sanitary
Sewer

V26025
FH7983

AR18356

Ex/ 30" RCP

247+00 248+00 249+00 250+00 251+00

V19067

Caution !!
Gas & OHP

V27768

Caution !!
UGT & FO

AR18355

Drainage Easement

WL Sta. 248+99.16, 20.93' Rt. =
Maize Rd. Sta. 56+69.75, 41.05' Rt.
Relocate FH, Extend 8' (E), H=6'
FH Bury Line Elev.=1324.66
Top Valve Box Elev.=1323.63
N=24854.887, E=51413.194
See Sht. No. WL02

STECKLINE COMMUNICATIONS INC.

ROBERT J. &
ANDA L.

ty Easement

FISHER, GAIL A. ETAL

DRAINAGE EASEMENT

WATER LINE

8" Fire Service Line

Connect to Ex. WL
45° Bend (Horiz.)

45° Bend (Horiz.)

Install 16"x2" Tee
2" Water Service Line

Prop. Ground @ ℄ WL

Ex. Ground @ ℄ WL

Prop. 42" RCP

Top Prop. 16" WL

Ex. 8" San. Sewer
℄=1314.1±

Ex. 30" SWS
℄=1314.2±

Top Ex. 16" WL

1335 1330 1325 1320 1315 1310 1305 1300

1317.81 +30.86 1317.66 +65.32 1317.66 +82.25 1317.66 +90.34

247+00 248+00 249+00 250+00 251+00

No.	Date	By	Approved	Revision
1	12/15/09	JPD	PAF	Removed Proposed 16" Line, Added 8" Line at Sta. 55+75

MAIZE ROAD
WEST KELLOGG AVE. TO PAWNEE AVE.
CITY OF WICHITA, KANSAS
WATER LINE P & P 247+60 to 249+00

POE & ASSOCIATES, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

FINAL

Engineer: P. FERGUSON
Designer: K. WARREN
KDOT Job No.: 87 N-0502-01 Poe Job No.: 1935
Date: SEPTEMBER 2009

Sheet
WL12 of W226