



**NOTE:**

In areas where severe pumping is encountered, it shall be at the City Engineer's discretion to require the Contractor to over excavate the unsuitable subgrade and replace as detailed "Unclassified Excavation Detail". The bid price "Unclassified Excavation" shall be paid for per Cubic Yard (C.Y.) and shall include all labor, equipment, dewatering (if needed), excavation, Geotextile (Mirafi HP 370), Crushed Rock, placing of materials and all incidentals to complete the item as directed by the City Engineer. The Contractor understands that a quantity of 500 C.Y. has been estimated for bidding purposes and is intended principally to serve as a guide in evaluating bids. Exact dimensions and quantities will be identified on an as-needed basis as determined by the City Engineer.

CITY OF WICHITA		KANSAS	
MERIDIAN AVENUE 31ST TO PAWNEE PROPOSED IMPROVEMENTS			
DESIGNED	J.R.L.	DRAWN	J.R.L.
CHECKED	B.A.L.	DATE	3/2005
DATE	1/27-2/1/05	SCALE	1" = 20'
PROJECT NO.	472-24712	SHEET NO.	3

WICHITA CORPORATION  
245 North Waco, Suite 420  
Wichita, Kansas 67202