STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	54–87 K–8258–09	2005	29	54

REMOVAL OF EXISTING STRUCTURES

LOCATION	STATION	DIST.	SIDE	ITEMS
North Frontage Rd.	3+091.110	15.989 m	Rt.	250 mm x 27.7 m Sanitary Sewer
North Frontage Rd.	3+113.755	32.095 m	Rt.	
North Frontage Rd.	3+113.755	32.095 m	Rt.	Manhole 3–4a (Phase I)
North Frontage Rd.	3+113.755	32.095 m	Rt.	250 mm x 223.28 m Sanitary Sewer
North Frontage Rd.	3+335.893	29.565 m	Rt.	
North Frontage Rd.	3+137.5	1.850 m	Rt.	1200 mm x 55.6 m Storm Sewer

Note: The items listed for removal may not be complete. Payment for items not listed but whose removal is required to accommodate construction of the proposed improvements, as determined by Engineer, shall not be paid for directly, but shall be included in the bid item "Removal of Existing Structures."

DATE | BY | REFERENCE NOTED | REFERENCE CHECKED

Plotted: | Drawn by: | File: | SCALE

CFS Cook, Flatt & Strobel ENGINEERS, P.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF
REMOVAL OF EXISTING STRUCTURES

City Of Wichita — Sedgwick, Co.

J:\00011ph2\North Frontage At Rusty Eck\29 Removals.dwg 10/3/2005 9:43:20 AM CDT