


61' B-B PAVEMENT DETAILS

STA. 14+03.53 TO STA. 20+27.67

FILL SECTION



TRANSVERSE SECTION

CUT SECTION




ELEVATION OFFSETS

DISTANCE FROM CENTERLINE (LT. & RT.)	
A. TOP OF SURFACE LIFT TO TOP OF CURBS	0' -0.54
B. TOP OF UPPER BASE LIFT TO TOP OF CURBS	2' -0.37
C. TOP OF LOWER BASE LIFT TO TOP OF CURBS	4' -0.12
D. TOP OF C.C. SUBGRADE TO TOP OF CURBS	6' -0.05
	8' -0.29
	10' -0.22
	12' -0.16
	14' -0.10
	16' -0.04
	18' 0.03
	20' 0.09
	22' 0.15
	24' 0.21
	26' 0.28
	27.5' 0.32
	29.5' 0.49
	30.5' 0.51
	31.5' 0.67
	31.5' 0.73
	31.5' 0.86
	31.5' 0.91
	31.5' 0.97
	31.5' 1.00
	31.5' 1.03



- CURB NOTES**
1. EXPANSION (ISOLATION) JOINTS SHALL BE CONSTRUCTED A MAXIMUM OF 300' APART AND AT ALL PIS, PIS, COLLECTOR QUADRANTS, AND ENDS OF RETURNS.
 2. MINIMUM OF 12" APART SHALL BE CONSTRUCTED A JOINT SEALER SHALL BE REQUIRED AT ALL JOINTS ON ARTERIAL AND INDUSTRIAL STREETS.



TRANSVERSE CONSTRUCTION JOINTS SHALL BE CONSTRUCTED IN FLEXIBLE BASE PAVEMENTS AT LOCATIONS WHERE SHOWN BY JOINT DETAILING PLANS ASSOCIATED WITH THE CONSTRUCTION OF THE TRANSVERSE JOINT SHALL BE INCLUDED IN THE BID PRICE FOR SQUARE YARDS 7" ASPHALTIC CONCRETE (5" BITUMINOUS BASE).

GENERAL NOTES

FABRIC REINFORCEMENT SHALL BE B X X 1100 GEOGRID AS MANUFACTURED BY TENSAR CORPORATION OR APPROVED EQUAL. FABRIC BASE REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. CRUSHED ROCK SHALL BE AS SPECIFIED IN SECTION 404 OF THE CITY OF WICHITA STANDARD SPECIFICATIONS.


ROCK BASE IS TO BE COMPACTED AND SMOOTHED WITH A STEEL FACED ROLLER PRIOR TO PLACEMENT OF ASPHALT. TACK COAT WILL NOT BE APPLIED TO ROCK BASE.

A TACK COAT OF EMULSIFIED ASPHALT (SS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQUARE YARD BETWEEN EACH LIFT OF ASPHALTIC MATERIAL.

BITUMINOUS BASE AND ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR LINE AND GRADE.


CONSTRUCTION JOINTS IN EACH LIFT SHALL BE STAGGERED A MINIMUM DISTANCE OF ONE (1) FOOT FROM JOINTS IN PRECEDING LIFTS AND PLACED SO THAT A JOINT WILL BE CONSTRUCTED ON THE CENTERLINE OF THE TOP LIFT.

THE ASPHALTIC CONCRETE PAVEMENT BETWEEN THE COMBINED CURB AND BITUMINOUS BASE SHALL BE PAID AS SQUARE YARDS OF 7" ASPHALTIC CONCRETE (5" BITUMINOUS BASE).



Gossell Livingston
 Architecture
 100 E. California Ave., Third Floor
 Oklahoma City, OK 73104
 Tel: (360) 265-4387
 Fax: (360) 265-5646
 Email: gossell@gliv.com

© 2016 Gossell Livingston Associates, Inc.
 The drawing and all information herein is the exclusive property of Gossell Livingston Associates, Inc. and is not to be copied or used in any way without the express written consent of Gossell Livingston Associates, Inc. All drawings, specifications, and schedules shall be subject to the original and applicable contract documents.



Johnson & Associates, Inc.
 100 E. California Ave., - Third Floor
 Oklahoma City, OK 73104
 (405) 235-8073 FAX (405) 235-8078
 Certificate of Authorization RE-1728 EXP. DATE: 12-31-2086

WICHITA WATERWALK PUBLIC IMPROVEMENTS PHASE 2 PACKAGE 2

No.	Date	Description
5.30.06		BID SET
4.27.06		FIELD CHECK SET

WATERMAN STREET TYPICAL PAVING SECTION

Job No.	P2.4
Date	05-30-06
Drawn	10
Checked	22 of 96