

BENCHMARK:  
 BM #3 - Cut in the Concrete Footing of a Steel Fence  
 Corner Post South of 37th Street North  
 Sta. 49+91, 48' Rt.  
 Elev. = 1329.25 MSL

Additional Grading May be Required for the SWS System to Drain Until the Bridge Grading is Complete. Additional Existing Rip Rap may be Re-Used Provided that Deletious Materials Have Been Removed and Subject to Engineer's Approval. Cost for this Work to be SUBSIDIARY to SWS Construction.

SCALE:  
 HORIZONTAL: 1" = 20'  
 VERTICAL: 1" = 5'

