SUMMARY OF PAVEMENT MARKINGS

LOCATION	4" Broken White Lane Line (ft)	6" Solid White Lane Line (ft)	12" White Diagonal Line (ft)	24" Solid White Stop Line (ft)	4" Broken Yellow Line (ft)	4" Solid Yellow Edge Line (ft)	4" Solid Yellow Double Line (ft)	12" Solid Yellow Diagonal Line (ft)	Left Turn Arrows (each)
Sta. 100+00 to Sta. 113+00	2481	143	0	318	0	0	1198	35	3
Sta. 113+00 to Sta. 132+48	3803	81	0	187	528	534	2246	152	6
Total	6284	224	0	505	528	528	3444	187	9

Scale: 1"=40'

LEGEND

○ Mount on Traffic Signal Pole

▼ Mount on Proposed Light Pole

No.	Revision	By	Date

WATERMAN STREET

SIGNING AND MARKING PLAN
STA. 100+00 TO STA. 113+00

JAMES L. ARMOUR, P.E.-CITY ENGINEER
CITY OF WICHITA PROJECT NO. 468-84167

Professional Engineering Consultants, P.A.
303 S. TOPEKA • WICHITA, KANSAS 67202
316-262-2691 • FAX 316-262-3003

Designed by	JPS	Job No.	06237	Sht. R57 of R111
Drawn by	DRP	Date	Feb., 2007	

DSNR: JPS OPER: DRP SCALE: 1"=40'
I:/2006/06237/MARKING/06237-000-MARKING100.DGN 9-26-2006 15:00:00 LAST REV: 2-24-2007 BY: DRP