STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0306-01	2005	55	111

SUMMARY OF PAVEMENT MARKINGS

LOCATION	4" Solid WHITE Edge Line	6" Broken WHITE Lane Line	6" Broken WHITE Lane Line (PCP)	6" Dotted WHITE Extension Line	6" Solid WHITE LANE LINE	8" Solid WHITE Gore Line	12" Solid WHITE Diagonal Line	12" Solid WHITE Chevron Line	12" Solid WHITE Type I Crosswalk Line	24" Solid WHITE Type II Crosswalk Line	24" Solid WHITE Stop Line	4" Solid YELLOW Edge Line	4" Solid YELLOW Double Line	4" Solid YELLOW Line	4" Broken YELLOW Line	12" Solid YELLOW Diagonal Line
29TH STREET NORTH - TYLER TO RIDGE	150	2,444												6,376	1,460	
TOTALS	150	2,444												6,376	1,460	

SUMMARY OF WORD & SYMBOL MARKINGS

LOCATION								STOP	ONLY	X-ING	SCHOOL
TOTALS											

NOTE: For specific pavement marking details and dimensions see plan sheets

NOTE: ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

RECAPITULATION OF QUANTITIES

ITEMS	TOTAL	UNITS
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(4")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(6")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(8")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(12")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(4")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(12")		ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(4" SOLID)	150	ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(6" BROKEN)	2444	ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(YELLOW)(4" SOLID)	6376	ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(YELLOW)(4" BROKEN)	1460	ft
		ft
PAVEMENT MARKING (EPOXY)(WHITE)(4")		ft
PAVEMENT MARKING (EPOXY)(WHITE)(6")		ft
PAVEMENT MARKING (EPOXY)(WHITE)(8")		ft
PAVEMENT MARKING (EPOXY)(WHITE)(12")		ft
PAVEMENT MARKING (EPOXY)(YELLOW)(4")		ft
PAVEMENT MARKING (EPOXY)(YELLOW)(12")		ft
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(12")		ft
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(24")		ft
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(YELLOW)(12")		ft
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING REMOVAL		ft

NOTE:

WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

PRIOR TO COMMENCEMENT OF PAVEMENT MARKING WORK THE ENGINEER WILL ESTABLISH THE LIMITS FOR "NO PASSING" ZONES. THESE LIMITS SHALL BE USED FOR THE LOCATION OF "NO PASSING" LINES AND FOR THE COMPUTATION OF ACTUAL MARKING QUANTITIES FOR THIS LINE TYPE.

NO.	DATE	REVISION	BY	APP'D
3				
2				
1				

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY AND RECAPITULATION OF PAVEMENT MARKING QUANTITIES

TE311

FHWA APPROVAL	04-29-03		APP'D	Linda G Voss	
DESIGNED	GJI	DETAILED	GJI	QUANTITIES	TRACED
DESIGN CK.	LGV	DETAIL CK.	LGV	QUAN. CK.	TRACE CK.

Plotted By : @@USERNAME@@ Thacher Bldg., 4th Floor
Plot File : @@@@@@@@@@UNSPEC@@@@@@@@@@
Plot Date : @@@@@SYSTIME@@@@@