


REMOVAL OF EXISTING STRUCTURES *		
STATION	SIDE	ITEM
142+50	RI.	650 L.F. Barbed Wire Fence
144+54	LI.	30" x 257" RCP w/End Section
147+17	LI.	Sign
147+29	LI.	2' x 4' Grate inlet

* For Information Only

- Utilities**
- Power: Westar Energy
 - Telephone: SBC
 - Water: Wichita Water and Sanitary Sewer
 - Water: Sedgwick County RWD No. 1
 - Sanitary Sewer: Wichita Water and Sanitary Sewer
 - Television: Cox Communication

- NW Cor. Sec. 3, T27S, R2E
- Fnd. #5 Bar with M.K.E.C. Survey Cap
 - N 1,705,120.0713 E 1,686,158.7785
 - @ Sta. 153+25.77
 - Chis. + on Top East End of Curb on N. Side of 29th St. 59.06' NW
 - Chis. + on Top East End of Curb on Median of 29th St. 59.06' NW
 - Clr. of Water Valve 67.66' ENE
 - 3 Nails on West Face of P.P. 109.89' NE
 - Mag Nail and Washer in Corner Post 70.53' SE

BM #220 Chis. a on N top of curb 28th St. N. on W side of Greenwich Rd. 28' W of manhole. Elev.=1385.17



No.	Revision	By	Date
GREENWICH ROAD			
PLAN			
STA. 142+50 TO STA. 149+00			
JAMES L. ARMOUR, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84415			
Professional Engineering Consultants, P.A.			
303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	JPS	Job No.	05777
Drawn by	DRP	Date	Feb., 2006
			SH. 5 of 81

DSNR: JPS OPER: DRP SCALE: 20
 I:\2005\05777\PLAN\05777-PL14250.DGN 2-2-2006 16:00:00 LAST REV: 8-31-2006 BY: svb