



NOTE:  
In areas where unstable or other unsuitable material is encountered, it shall be at the City Engineer's discretion to require the Contractor to over excavate the material and replace it as detailed "Unclassified Excavation Detail". The Engineer prior to work shall approve the excavation. The bid price for "Unclassified Excavation" shall include all labor, equipment, dewatering (if needed), excavation geotextile (Mirafi Geolon HP370, or approved equal), crushed rock, placing of all materials, and all incidentals to complete the item as directed by the City Engineer. The Contractor understands that a quantity has been estimated for bidding purposes and is intended principally to serve as a guide in evaluating bids. The Engineer will determine the exact dimensions and quantities. When the quantity of Unclassified Excavation underruns or overruns the contract quantity, the work shall be performed at the contract unit price and no alteration or variation in the contract unit price will be considered. Quantities of Unclassified Excavation will not be measured for payment when the subgrade has become unstable or unsuitable because of negligence or improper methods of construction by the Contractor. However, the Contractor will be required to correct these conditions.

CITY OF WICHITA		PAWNEE STREET	
MERIDIAN AVE. TO SENECA ST.		PAWNEE STREET	
TYPICAL SECTIONS		STA. 13+74.08 TO STA. 54+85.40	
WICHITA	KANSAS	DESIGNED	J.R.L.
		CHECKED	B.A.L.
		DATE	9/11/2006
		SCALE	1"=20'
		SHEET NO.	4

65\W04\0011\road\typ02.sht  
 9/11/2006 1:41:51 PM