


PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
472-84118	2005	44	79

LOCATION	TENTH POINT	LEFT FASCIA			CROWN GRADE			RIGHT FASCIA		
		STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION
⊕ Abutment #1	1.000	45+93.57	-32.000	1266.44	45+85.00	0.000	1266.88	45+76.43	32.000	1266.32
	1.100	45+97.17	-32.000	1266.46	45+88.60	0.000	1266.90	45+80.03	32.000	1266.35
	1.200	46+00.77	-32.000	1266.49	45+92.20	0.000	1266.93	45+83.63	32.000	1266.37
	1.300	46+04.37	-32.000	1266.51	45+95.80	0.000	1266.95	45+87.23	32.000	1266.40
	1.400	46+07.97	-32.000	1266.53	45+99.40	0.000	1266.98	45+90.83	32.000	1266.42
	1.500	46+11.57	-32.000	1266.55	46+03.00	0.000	1267.00	45+94.43	32.000	1266.44
	1.600	46+15.17	-32.000	1266.56	46+06.60	0.000	1267.02	45+98.03	32.000	1266.47
	1.700	46+18.77	-32.000	1266.58	46+10.20	0.000	1267.04	46+01.63	32.000	1266.49
	1.800	46+22.37	-32.000	1266.59	46+13.80	0.000	1267.06	46+05.23	32.000	1266.51
	1.900	46+25.97	-32.000	1266.60	46+17.40	0.000	1267.07	46+08.83	32.000	1266.53
⊕ Pier #1	2.000	46+29.57	-32.000	1266.61	46+21.00	0.000	1267.08	46+12.43	32.000	1266.55
⊕ Pier #1	2.000	46+29.57	-32.000	1266.61	46+21.00	0.000	1267.08	46+12.43	32.000	1266.55
	2.100	46+34.37	-32.000	1266.61	46+25.80	0.000	1267.10	46+17.23	32.000	1266.57
	2.200	46+39.17	-32.000	1266.62	46+30.60	0.000	1267.11	46+22.03	32.000	1266.59
	2.300	46+43.97	-32.000	1266.62	46+35.40	0.000	1267.11	46+26.83	32.000	1266.60
	2.400	46+48.77	-32.000	1266.61	46+40.20	0.000	1267.12	46+31.63	32.000	1266.61
	2.500	46+53.57	-32.000	1266.61	46+45.00	0.000	1267.12	46+36.43	32.000	1266.62
	2.600	46+58.37	-32.000	1266.60	46+49.80	0.000	1267.11	46+41.23	32.000	1266.62
	2.700	46+63.17	-32.000	1266.58	46+54.60	0.000	1267.10	46+46.03	32.000	1266.62
	2.800	46+67.97	-32.000	1266.56	46+59.40	0.000	1267.09	46+50.83	32.000	1266.61
	2.900	46+72.77	-32.000	1266.54	46+64.20	0.000	1267.08	46+55.63	32.000	1266.60
⊕ Pier #2	3.000	46+77.57	-32.000	1266.52	46+69.00	0.000	1267.06	46+60.43	32.000	1266.59
⊕ Pier #2	3.000	46+77.57	-32.000	1266.52	46+69.00	0.000	1267.06	46+60.43	32.000	1266.59
	3.100	46+81.17	-32.000	1266.50	46+72.60	0.000	1267.04	46+64.03	32.000	1266.58
	3.200	46+84.77	-32.000	1266.47	46+76.20	0.000	1267.02	46+67.63	32.000	1266.57
	3.300	46+88.37	-32.000	1266.45	46+79.80	0.000	1267.00	46+71.23	32.000	1266.55
	3.400	46+91.97	-32.000	1266.42	46+83.40	0.000	1266.98	46+74.83	32.000	1266.53
	3.500	46+95.57	-32.000	1266.39	46+87.00	0.000	1266.96	46+78.43	32.000	1266.51
	3.600	46+99.17	-32.000	1266.36	46+90.60	0.000	1266.93	46+82.03	32.000	1266.49
	3.700	47+02.77	-32.000	1266.32	46+94.20	0.000	1266.90	46+85.63	32.000	1266.47
	3.800	47+06.37	-32.000	1266.29	46+97.80	0.000	1266.87	46+89.23	32.000	1266.44
	3.900	47+09.97	-32.000	1266.26	47+01.40	0.000	1266.84	46+92.83	32.000	1266.41
⊕ Abutment #2	4.000	47+13.57	-32.000	1266.23	47+05.00	0.000	1266.80	46+96.43	32.000	1266.38

Note:
Stations and Offsets are referenced to the ⊕ Hydraulic Avenue. Negative values for Offsets are measured left of the centerline.

drawn by : msn
 plotted by : ras 9-9-2005
 Drawing Name : I:\9999\99764\off1cecheck\99764_C-P\mtele\EP\171.dgn

No.	Revisions	By	Date
CITY OF WICHITA BR. NO. 5304008700LBS05 STA. 46+45.00 55TH AND HYDRAULIC AVE. PAVEMENT ELEVATIONS PROJECT NO. 472-84118 SEDGWICK COUNTY			
 Professional Engineering Consultants, P.A. <small>303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003</small>			
Designed by	M.S.N.	Checked by	R.A.S.
Drawn by	M.S.N.	Date	July 2005 Job No. 99764