



EROSION CONTROL MEASURE	INSTALL	MAINTAIN	REMOVE
SILT FENCE (LF)	0	294	0
STRAW BALE BARRIER (EA)	0	0	0
DROP INLET BARRIER (EA)	0	0	0
CURB INLET BARRIER (EA)	0	0	0
TURF REINFORCEMENT MAT (SY)	0	0	0
BACK OF CURB PROTECTION (SY)	0	0	0
EROSION CONTROL BERM (LF)	0	0	0
TEMPORARY DITCHING (LS)	0	0	0
CONSTRUCTION ENTRANCE (EA)	0	1	0

QUANTITIES ARE FOR INFORMATION ONLY! CONTRACTOR SHALL VERIFY QUANTITIES PER FINAL BID QUANTITY SHEET.

* ALL EXISTING BMPs INCLUDING CONSTRUCTION ENTRANCE, SEDIMENT BARRIERS, SILT FENCE, CUT-OFF TRENCH, AND EROSION CONTROL MAT SHALL BE MAINTAINED AND REPAIRED IF NECESSARY. REPLACEMENT OR REMOVAL OF EROSION CONTROL MEASURES TO BE PAID FOR BY L.S. BID ITEM "MAINTAIN EXISTING EROSION CONTROL BMPs"

EROSION CONTROL PLAN LEGEND
(Installation Details Found in the SWP2 Plan)

- DROP INLET PROTECTION
- CURB INLET PROTECTION
- DITCH CHECKS
- SILT FENCING
- CUT-OFF TRENCH
- BACK OF CURB PROTECTION
- EROSION CONTROL MAT
- TEMPORARY DITCH

NO SCALE

—1435— Existing Grade

	STEVE KELLEY 6TH ADDITION EROSION CONTROL PLAN/ESM'T GRADING STREET PAVING IMPROVEMENTS	
	<small>Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE</small>	
PROJECT NUMBER	DESIGN	DRAWN
	TJW	TJW
REVISIONS:	APPROVED	DATE
	NBW	May 2010
	SCALE	
	Noted	
	SHEET	
		7 OF 14