



Construct 4.26m Std. Commercial Concrete Full Ramp Drive (200mm) See Drive Detail Sheet.
 Construct 6.70m Std. Commercial Concrete Full Ramp Drive (200mm) See Drive Detail Sheet.
 Saw, Remove & Replace A.C. Parking Pmnt as shown

REMOVAL LEGEND:	
Existing Asphalt and Concrete Pavement to be Removed (Includes Curb & Gutter):	Existing Sidewalk, Driveway, & Parking (Asphalt & Concrete) Pavement to be Removed:

BENCHMARK
 BM #5 - Top of Brick NW Corner of Brick Planter NW Corner Bldg. #162 SE Corner of Hillside & 1st. Sta. 0+988.819, 22.336m Rt. Elev. = 40.685 SI Units (133.48 City Datum)

NOTE:
 Trees/Shrubs to be removed are marked thus:



PROJECT NUMBER 472-83862		SHEET NAME PAV06		ENGINEERING DIRECTORY F:\HillsideLand\dwg	
DESIGN ATD	DRAWN Sonny	APPROVED JFB	DATE May 2006	SCALE Noted	BAUGHMAN NO 01-03-E947

CAPITAL IMPROVEMENT PROJECT
HILLSIDE AVENUE PAVING
 Sta. 0+920.000 to Sta. 1+060.000

	BAUGHMAN COMPANY, P.A.	SHEET 16
	ENGINEERING, SURVEYING, & PLANNING	OF 118

316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

CAUTION!
 Top of Prop SWS Pipe in Rock Base

* Removal of Existing Concrete Steps & Walls is to be Paid for as "Removal of Existing Structures".

** Construction of Steps to be SUBSIDIARY to the Bid Item "Sidewalk Concrete (100mm)". See Misc. Pmnt. Details