



Field observations of the existing traffic manhole south of the north drive to the College Hill Square Shopping Center indicates that a 50mm RGC Conduit has been extended across the concrete drive with the Central and Hillside Intersection Project. The Signal Contractor shall attempt to locate the end of the existing 50mm RGC, construct an Interconnect Traffic Manhole, and splice into the existing Interconnect cable coiled in the existing traffic manhole. If the existing 50mm RGC is not located, the Signal Contractor shall bore across the existing concrete drive and splice into the existing Interconnect system in the existing traffic manhole. Cost associated with connecting the proposed and existing Interconnect systems shall not be paid for directly, but shall be considered SUBSIDIARY to the Lump Sum Bid Item "Traffic Signal Interconnect".

