STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0353-01	2005	97	162

SUMMARY OF PAVEMENT MARKINGS

LOCATION	4" Solid WHITE Edge Line	6" Solid WHITE Edge Line	6" Broken WHITE Lane Line	6" Broken WHITE Lane Line (PCP)	6" Dotted WHITE Extension Line	6" Solid WHITE LANE LINE	8" Solid WHITE Gore Line	12" Solid WHITE Diagonal Line	12" Solid WHITE Chevron Line	12" Solid WHITE Type I Crosswalk Line	24" Solid WHITE Type II Crosswalk Line	24" Solid WHITE Stop Line	4" Solid YELLOW Edge Line	4" Solid YELLOW Double Line	4" Solid YELLOW Line	4" Broken YELLOW Line	6" Solid YELLOW Edge Line	12" Solid YELLOW Diagonal Line
Pawnee Avenue	*761.5*		*9,641.7*			*850.0*				*362.3*		*121.3*		*2,271.5*	*5,060.4*	*5,060.4*		*98.5*
119th Street West	*1,818.3*					*200.0*								*1,437.4*				*154.0*
Maize Road	*1,607.9*					*213.6*								*1,286.8*				*104.8*
TOTALS	*4,187.7*		*9,641.7*			*1,263.6*				*362.3*		*121.3*		*4,995.7*	*5,060.4*	*5,060.4*		*357.3*

RECAPITULATION OF QUANTITIES

ITEMS	TOTAL	UNITS
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(4")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(6")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(8")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(12")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(4")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(6")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(12")		ft
		EACH
		EACH
		EACH
		EACH
PAVEMENT MARKING (WHITE)(4")	4,188	ft
PAVEMENT MARKING (WHITE)(6")	3,674	ft
PAVEMENT MARKING (WHITE)(8")		ft
PAVEMENT MARKING (WHITE)(12")		ft
PAVEMENT MARKING (YELLOW)(4")	16,318	ft
PAVEMENT MARKING (YELLOW)(6")		ft
PAVEMENT MARKING (YELLOW)(12")		ft
PAVEMENT MARKING (INTERSECTION GRADE)(WHITE)(12")	363	ft
PAVEMENT MARKING (INTERSECTION GRADE)(WHITE)(24")	122	ft
PAVEMENT MARKING (INTERSECTION GRADE)(YELLOW)(12")	358	ft
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)(Lt-Turn Arrow)	33	EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)(Rt-Turn Arrow)	4	EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)("ONLY")	4	EACH
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(6")		ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(8")		ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(12")		ft
PAVEMENT MARKING REMOVAL		ft

SUMMARY OF WORD & SYMBOL MARKINGS

LOCATION	↑↱	↰↑	↑	↱	↰	♿	RR	STOP	ONLY	X-ING	SCHOOL
Pawnee Avenue				*4*	*23*				*4*		
119th Street West					*4*						
Maize Road					*6*						
TOTALS				*4*	*33*				*4*		

NOTE: For specific pavement marking details and dimensions see plan sheets

NOTE: ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

PAVEMENT MARKING GENERAL NOTE

All pavement markings shall be thermoplastic, unless otherwise approved by the Engineer. Pavement markings shall be installed per manufacturer's recommendations and shall meet KDOT's 90M-100-R10 specification (City Standard Specifications). Full traffic may not be restored (and substantial project completion achieved) until all pavement markings are in place. Should construction timing be such that restoration of traffic becomes necessary during temperatures prohibiting the installation of thermoplastic markings, the contractor shall install and maintain temporary markings until such time that thermoplastic markings may be properly installed. Except for the material requirement, temporary pavement markings shall be placed equivalent, in every manner (i.e. dimension, frequency, spacing, etc.), to the permanent marking layout. The cost for temporary pavement markings will not be paid for directly, but shall be considered subsidiary to the bid item for "Pavement Markings".

NOTE:

WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

PRIOR TO COMMENCEMENT OF PAVEMENT MARKING WORK THE ENGINEER WILL ESTABLISH THE LIMITS FOR "NO PASSING" ZONES. THESE LIMITS SHALL BE USED FOR THE LOCATION OF "NO PASSING" LINES AND FOR THE COMPUTATION OF ACTUAL MARKING QUANTITIES FOR THIS LINE TYPE.

NO.	DATE	REVISION	BY	APP'D
3				
2				
1	07/26/2005	New FHWA Approval Date	JFF	BDG

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY AND RECAPITULATION OF PAVEMENT MARKING QUANTITIES

~~TE311~~

FHWA APPROVAL	07/26/2005	APP'D Brian D. Gower	
DESIGNED JFF	DETAILED JFF	QUANTITIES	TRACED
DESIGN CK. BDG	DETAIL CK. BDG	QUAN. CK.	TRACE CK.

Sheet No.

Plotted By : $$USERNAME$$ $$$KDOTGRP$$$$, 6th Floor
Plot File : $$$$$$$$$$$DGNSPEC$$$$$$$$$$$$$$
Plot Date : $$$$$SYTIME$$$$$$