MATCH LINE SEE SHEET LM-207

LEVEE C

ALTERNATE BID ITEM
AREA 2 – TREE REMOVAL,
REMOVE TREES

BID ITEM
AREA 2 – TREE REMOVAL,
REMOVE ALL TREES IN THIS AREA.
METAL A-JAX – ANY "JAX" DAMAGED BY TREE REMOVAL ACTIVITY SHALL BE REPAIRED, IN KIND, AT THE CONTRACTORS EXPENSE.

ALTERNATE BID ITEM
AREA 2 – TREE REMOVAL,
REMOVE TREES

W 73RD ST N

N TYLER RD

W 69TH ST N

N MAIZE RD

LEVEE C

N

300' 150' 0 300'

SCALE: 1" = 300'

NOTES:

1. MAXIMUM ALLOWABLE FENCE REPLACEMENT LENGTHS ARE SPECIFIED FOR EACH AREA. IF A NOT-TO-EXCEED LENGTH IS NOT SPECIFIED IT SHALL BE ASSUMED THAT FENCE REPLACEMENT IS NOT ANTICIPATED FOR THE SPECIFIED AREA. ANY ADDITIONAL FENCING REQUIRED, DUE TO DAMAGE DURING TREE REMOVAL, THAT EXCEEDS THE MAXIMUM LENGTH SPECIFIED SHALL BE REPLACED IN-KIND AT THE CONTRACTORS EXPENSE UNLESS OTHERWISE AUTHORIZED BY THE CITY OF WICHITA'S INSPECTOR.
2. ROOTBALL EXTRACTION ON TREES TO BE REMOVED THAT ARE GREATER THAN 15' FROM THE TOE OF THE LEVEE MAY BE CUT FLUSH WITH GROUND SURFACE AND TREATED TO PREVENT FUTURE GROWTH. SEE SHEETS G-1.02 AND G-1.03.

MATCH LINE SEE SHEET LM-204

MATCH LINE SEE SHEET LM-205

| MARK | DESCRIPTION | DATE | APPR. |
|---|---|---|---|
| | | | |


amec

AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-2810
Fax: (785) 272-2878


CITY OF WICHITA

SYSTEMWIDE VEGETATION MAINTENANCE - PHASE 1
WICHITA-VALLEY CENTER LOCAL
FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE
LICENSED
15855
5-28-10
KANSAS
PROFESSIONAL ENGINEER

| | | |
|---|---|---|
| DESIGNED BY: Larry Sample, PE | | DATE: 5-28-2010 |
| DWN BY: DSM | CKD BY: LBK | APP BY: L. SAMPLE |
| FILE NAME: 561500000-LM-206.dgn | | |
| AMEC PROJ. NO. 5-6150-0000 | | |

AREA 2

LM-2.06

SHEET 13 OF 38