STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	54–87 K–8258–01	2007	114	556

SCHEDULE OF INLETS & MANHOLES

STRUCT. NO.	STATION	LOCATION	OFFSET DIST.	OFFSET SIDE	GRATE INLET SPECIAL	CURB INLET TYPE 10	STD. TYPE P MH	PRE CAST MH	CURB INLET TYPE I	DROP INLET	CURB INLET TYPE IA		PIPE DATA: INFLOW PIPES SIZE (mm)	INFLOW PIPES FL EL.	INFLOW PIPES SIZE (mm)	INFLOW PIPES FL EL.	INFLOW PIPES SIZE (mm)	INFLOW PIPES FL EL.	OUTFLOW PIPE SIZE (mm)	OUTFLOW PIPE FL EL.	OUTFLOW PIPE SL. (%)	STRUCTURE INFO. TOP ELEV.	FLOOR ELEV.	H mm	W mm	L mm	STEPS (No.)	STORM SEWER RCP (m) -- (mm)	375 (mm)	450 (mm)	600 (mm)	750 (mm)	900 (mm)	1050 (mm)	1200 (mm)	1350 (mm)	1500 (mm)	1650 (mm)	2100 (mm)	RCPHE ✻(1) (mm)	Ht. Fill (m)	Remarks
281	2+920.000	Kellogg Avenue	1.000	Rt.			1						375(S)	411.282	600(E)	411.147			600(N)	411.057	0.755	413.138									26.1										
282	2+960.000	Kellogg Avenue	1.000	Rt.			1						375(N)	411.616	375(S)	411.616	600(E)	411.448	600(W)	411.387	0.623	413.794									38.5										
283	3+000.000	Kellogg Avenue	1.000	Rt.			1						375(N)	412.251	375(S)	412.251	600(E)	412.080	600(W)	411.990	1.408	414.450									38.5										
284	3+040.000	Kellogg Avenue	1.000	Rt.			1						375(N)	412.795	375(S)	412.795	600(E)	412.660	600(W)	412.570	1.273	415.106									38.5										
285	3+080.000	Kellogg Avenue	1.000	Rt.			1						375(N)	413.265	375(S)	413.265	600(E)	412.840	600(W)	412.840	0.468	415.757									38.5										
286	3+120.000	Kellogg Avenue	1.000	Rt.			1						375(N)	413.400	375(S)	413.400	450(E)	413.240	600(W)	413.000	0.416	416.300									38.5										
287	3+160.000	Kellogg Avenue	1.000	Rt.			1						375(N)	413.775	375(S)	413.775	450(E)	413.490	450(W)	413.400	0.415	416.693								38.6										
288	3+200.000	Kellogg Avenue	1.000	Rt.			1						375(N)	414.000	375(S)	414.000	450(E)	413.740	450(W)	413.650	0.412	416.935								38.8										
313	3+300.000	Kellogg Avenue	1.000	Rt.			1						375(N)	414.500	375(S)	414.500	450(E)	414.200	450(W)	414.140	0.405	416.880								98.8										
312	3+329.000	Kellogg Avenue	1.000	Rt.			1						375(N)	414.480	375(S)	414.500			450(W)	414.345	0.522	416.638								27.8										
330	3+420.000	Kellogg Avenue	1.000	Rt.			1						375(N)	413.378	375(S)	413.378			375(E)	413.288	1.668	415.572							38.8											
329	3+460.000	Kellogg Avenue	1.000	Rt.			1						375(N)	412.641	375(S)	412.641	375(W)	412.641	450(E)	412.551	2.250	414.835								38.8										
328	3+500.000	Kellogg Avenue	1.000	Rt.			1						375(N)	411.753	375(S)	411.753	450(W)	411.678	450(E)	411.588	2.433	413.947								38.8										
327	3+540.000	Kellogg Avenue	1.000	Rt.			1						375(N)	410.719	375(S)	410.719	450(W)	410.644	450(E)	410.554	2.554	412.913								38.6										
326	3+580.000	Kellogg Avenue	1.000	Rt.			1								375(S)	409.643	450(W)	409.568	600(N)	409.328	2.604	411.837									16.9									
366	3+620.000	Kellogg Avenue	1.000	Rt.			1						375(N)	408.040	375(S)	408.174			375(E)	407.980	1.987	410.760							43.8											
365	3+665.000	Kellogg Avenue	1.000	Rt.			1						375(N)	407.110	375(S)	407.151	375(W)	407.110	450(E)	406.975	2.539	409.550								43.8										
364	3+710.000	Kellogg Avenue	1.000	Rt.			1						375(N)	405.938	375(S)	405.982	450(W)	405.863	450(E)	405.778	2.477	408.339								43.8										
363	3+755.000	Kellogg Avenue	1.000	Rt.			1						375(N)	404.768	375(S)	404.814	450(W)	404.693	450(E)	404.638	2.598	407.130								38.6										
362	3+795.000	Kellogg Avenue	1.000	Rt.			1						375(N)	403.874	375(S)	403.922	450(W)	403.635	600(E)	403.395	2.688	406.201									38.5									
361	3+835.000	Kellogg Avenue	1.000	Rt.			1						375(N)	403.215	375(S)	403.265	600(W)	402.360	600(E)	402.302	2.622	405.508									34.4									
390	3+875.000	Kellogg Avenue	20.234	Lt.	1								375(N)	401.069	375(S)	401.069						405.064							17.6											
391	3+875.000	Kellogg Avenue	19.795	Rt.	1								375(N)	401.069	375(S)	401.069						405.064							17.3											
392	3+910.000	Kellogg Avenue	19.070	Lt.	1								375(N)	400.981	375(S)	400.981						404.857							16.4											
393	3+910.000	Kellogg Avenue	19.795	Rt.	1								375(N)	400.981	375(S)	400.981						404.857							17.3											
394	3+932.538	Kellogg Avenue	18.321	Lt.	1								375(N)	400.924	375(S)	400.924						404.820							15.7											
395	3+932.538	Kellogg Avenue	19.795	Rt.	1								375(N)	400.924	375(S)	400.924						404.820							17.3											
396	3+955.000	Kellogg Avenue	17.574	Lt.	1								375(N)	400.869	375(S)	400.869						404.857							14.9											
397	3+955.000	Kellogg Avenue	19.795	Rt.	1								375(N)	400.869	375(S)	400.869						404.857							17.3											
398	3+990.000	Kellogg Avenue	16.820	Lt.	1								375(N)	400.804	375(S)	400.804						405.063							14.1											
399	3+990.000	Kellogg Avenue	19.795	Rt.	1								375(N)	400.804	375(S)	400.804						405.063							17.3											
441	4+030.000	Kellogg Avenue	1.000	Rt.			1						375(N)	403.324	375(S)	403.305	450(E)	401.781	450(W)	401.691	2.403	405.506								34.0										
442	4+075.000	Kellogg Avenue	1.000	Rt.			1						375(N)	404.074	375(S)	404.095	450(E)	402.916	450(W)	402.825	2.384	406.256								43.8										
443	4+125.000	Kellogg Avenue	1.000	Rt.			1						375(N)	404.939	375(S)	404.950	375(E)	404.167	450(W)	404.076	2.377	407.121								48.8										
444	4+175.000	Kellogg Avenue	1.000	Rt.			1						375(N)	405.804	375(S)	405.815	375(E)	405.417	375(W)	405.327	2.377	407.986							48.8											
445	4+225.000	Kellogg Avenue	1.000	Rt.			1						375(N)	406.668	375(S)	406.680			375(W)	406.578	2.379	408.851							48.8											
4101	49+699.000	Rock Road	19.381	Rt.					1										375(S)	411.807	0.510	413.485							50.7											
4101A	49+751.212	Rock Road	22.162	Rt.					1				375(N)	411.548					450(S)	411.473	0.510	412.913								27.3										
4102	49+780.000	Rock Road	22.400	Rt.					1				450(N)	411.334					450(S)	411.260	0.510	412.949								68.5										
4104	49+850.000	Rock Road	23.106	Rt.					1				450(N)	410.910					600(S)	410.760	0.726	413.031									43.5									
4106	49+895.000	Rock Road	23.387	Rt.					1				600(N)	410.444					600(S)	410.354	0.726	412.794									47.9									
4107	49+945.179	Rock Road	23.809	Rt.					1				600(N)	410.006					750(S)	409.856	0.485	412.455										19.8								
1181	3+845.000	North Frontage Rd.	1.850	Rt.									750(N)	409.760	750(E)	409.700			900(W)	409.520	0.472	412.529																		
4100	49+850.000	Rock Road	14.079	Lt.					1										450(S)	411.050	0.616	413.211								43.5										
4103	49+895.000	Rock Road	15.218	Lt.					1				450(N)	410.780					450(S)	410.690	0.501	412.958								44.8										
4105	49+945.178	Rock Road	16.429	Lt.					1				450(N)	410.460	375(NE)	410.625			600(S)	410.310	0.723	412.602									22.4									
4108	49+938.217	Rock Road	49.817	Lt.						1									375(SW)	411.000	1.22	412.500*							30.7											*FIELD VERIFY
1182	3+894.000	North Frontage Rd.	1.850	Rt.									. 600(N)	410.136	750(E)	409.926			750(W)	409.896	0.414	412.781																		
4201	50+086.831	Rock Road	–	Rt.			1		1													**																		
3450	50+095.000	Armour Road	14.837	Lt.			1		1										375(W)	406.661	3.000	402.2±							3.2											
3451	50+095.000	Armour Road	10.200	Lt.			1		1				375(E)	406.565					375(W)	406.266	1.000	407.640							25.8											
3452	50+109.700	Armour Road	10.200	Rt.			1		1				375(E)	406.007					375(W)	405.917	2.000	407.422							2.5											
3453	50+170.818	Armour Road	12.111	Lt.			1		1										375(W)	405.852	3.000	407.5±							4.5											
3454	50+169.513	Armour Road	7.470	Lt.			1		1				375(E)	405.717					375(W)	405.417	1.000	406.792							14.8											
3455	50+161.810	Armour Road	7.180	Rt.			1		1				375(E)	405.269					375(W)	405.179	2.000	406.841							7.5											
		TOTALS			10		33	–	10	1																			485.1	757.1	422.2	19.8								

**CONST. OVER EXISTING PIPE

*FIELD VERIFY

DATE | BY | REFERENCE NOTED | REFERENCE CHECKED

Plotted: | Drawn by: | File: 114

Cook, Flatt & Strobel ENGINEERS, P.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF INLETS & MANHOLES
KELLOGG, ROCK ROAD, AND ARMOUR

J:\00011PH2 FINAL\DRAINAGE\SCHEDULE OF INLETS.dwg 1/9/2006 2:41:51 PM CST