STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	54–87 K–8258–01	2007	240	556

WALL N1 REINFORCING STEEL SUMMARY

PANEL	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.
A	WH1	51	WV1	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
B	WH1	51	WV2	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
C	WH1	49	WV3	50	WT1	25	CH1	10	CS2	50	CTF2	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
D	WH1	49	WV4	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
E	WH1	47	WV5	50	WT1	25	CH1	10	CS2	50	CTF2	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
F	WH1	47	WV6	50	WT1	25	CH1	10	CS2	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
G	WH1	45	WV7	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
H	WH1	45	WV8	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
I	WH1	43	WV9	50	WT1	25	CH1	10	CS2	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
J	WH1	41	WV10	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
K	WH1	41	WV11	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
L	WH1	39	WV12	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
M	WH1	37	WV13	50	WT1	25	CH1	10	CS2	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
N	WH1	35	WV14	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
O	WH1	35	WV15	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
P	WH1	33	WV16	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
Q	WH1	31	WV17	50	WT1	25	CH1	10	CS2	50	CTF2	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
R	WH1	29	WV18	50	WT1	25	CH1	10	CS2	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
S	WH1	29	WV19	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
T	WH1	27	WV20	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
U	WH1	25	WV21	50	WT1	25	CH1	10	CS2	50	CTF2	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
V	WH1	23	WV22	50	WT1	25	CH1	10	CS2	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
W	WH1	23	WV23	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
X	WH1	21	WV24	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
Y	WH1	19	WV25	50	WT1	25	CH1	10	CS2	50	CTF2	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
Z	WH1	17	WV26	50	WT1	25	CH1	10	CS2	50	CTF2	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
AA	WH1	15	WV27	50	WT1	25	CH1	10	CS2	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
BB	WH1	15	WV28	50	WT1	25	CH1	10	CS1	50	CTF1	25	CTB1	25	BH1	10	BV1	25	BCV1	25	BWV1	25
CC	WH1	20	WBV1	25	WFV1	25	WT2	25							BH1	6	BV1	25				
DD	WH1	23	WBV2	25	WFV2	25	WT2	25							BH1	6	BV1	25				
EE	WH1	26	WBV3	25	WFV3	25	WT2	25							BH1	6	BV1	25				
FF	WH1	29	WBV4	25	WFV4	25	WT2	25							BH1	6	BV1	25				

WALL N2 REINFORCING STEEL SUMMARY

PANEL	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.	MARK	NO.
A	WH1	55	WV1	56	WT1	28	CH1	10	CS1	56	CTF2	28	CTB1	28	BH1	10	BV1	28	BCV1	28	BWV1	28
B	WH2	55	WV2	50	WT1	25	CH2	10	CS2	50	CTF2	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
C	WH2	55	WV3	50	WT1	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
D	WH2	55	WV4	50	WT1	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
E	WH2	55	WV5	50	WT1	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
F	WH2	55	WV6	50	WT1	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
G	WH2	55	WV7	50	WT1	25	CH2	10	CS1	50	CTF2	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
H	WH2	55	WV8	50	WT1	25	CH2	10	CS2	50	CTF2	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
I	WH2	53	WV9	50	WT2	25	CH2	10	CS2	50	CTF2	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
J	WH14	134	WV10	50	WT2	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
K	WH2	55	WV11	50	WT2	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
L	WH2	55	WV12	50	WT2	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
M	WH2	53	WV13	50	WT2	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
N	WH2	53	WV14	50	WT2	25	CH2	10	CS2	50	CTF2	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
O	WH2	51	WV15	50	WT2	25	CH2	10	CS2	50	CTF2	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
P	WH2	51	WV16	50	WT2	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25
Q	WH2	51	WV17	50	WT2	25	CH2	10	CS1	50	CTF1	25	CTB1	25	BH2	10	BV1	25	BCV1	25	BWV1	25

RETWALL/DETAILS 1:200

KANSAS DEPARTMENT OF TRANSPORTATION

ROCK ROAD RETAINING WALLS
REINFORCING SUMMARY

Proj. No. 54–87 K–8258–01 SEDGWICK COUNTY

CFS
Cook, Flatt & Strobel
ENGINEERS, P. A.

DESIGNED	R.S.C.	SCALE	Noted
DETAILED	T.R.G.	DATE	
QUANTITIES	T.R.G.	SHEET	21 OF 27