

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	54-87 K-8258-01	2007	381	556

SYMBOL KEY

-  REMOVE SIGN
-  REMOVE POST
-  REMOVE FOOTING
-  REMOVE SIGN & POST
-  REMOVE POST & FOOTING
-  REMOVE SIGN, POST, & FOOTING
-  MOUNT ON WOOD POST IN CONCRETE FOOTING
-  MOUNT ON WOOD POST IN SOIL
-  MOUNT ON STEEL BEAM BREAKAWAY POST
-  MOUNT ON STEEL U-POST
-  MOUNT ON PERFORATED SQUARE STEEL TUBE
-  MOUNT ON EXISTING POST
-  MOUNT ON VERTICAL SUPPORT
-  SHOULDER MOUNTED INSTALLATION
-  OFFSET MOUNTED INSTALLATION
-  EXISTING SIGN
-  EXISTING SIGN TO BE OVERLAID
-  SIGN IS NOT PART OF PROJECT
-  TYPE 'A' DELINEATOR (RIGID)
-  TYPE 'B' DELINEATOR (RIGID)
-  TYPE 'A' DELINEATOR (FLEXIBLE)
-  TYPE 'B' DELINEATOR (FLEXIBLE)
-  TYPE 2 OBJECT MARKER
-  TYPE 3 OBJECT MARKER

GENERAL NOTES

In order to expedite the completion of the project for traffic service, the Signing and Delineator work shall be sequenced with any other contract work such that the phases of construction may proceed and be completed at the same time.

New signs erected on the project which are in conflict with existing signing are to be completely covered until the existing signs are removed or the new signing is applicable. The existing signs that are being replaced, removed, or do not follow the current MUTCD signing standards are to be removed when the project is completed or as determined by the Engineer.

The contractor shall exercise caution at all times when installing sign supports in and around areas where utilities exist, either underground or overhead, and will be held responsible for any damage incurred to the system. The installation of sign supports shall include the excavation, drilling, or driving the support footing and the erection of the sign support. The contractor shall exercise caution when working around any existing signs that are to remain and will be held responsible for any damage to the signs, supports, or footings. The contractor shall exercise care when working around shrubbery while removing or installing signs or sign supports.

An existing sign post installation shall be plumb and the compaction of the backfill soil shall comply with the specifications after the removal and resetting of a sign, the removal and replacement of a sign, or the installation of a new sign.

The Contractor shall provide mounting bolts that are of a length that does not extend more than a nominal 1 inch beyond the sign post. The Contractor shall not make any field modifications to the mounting bolt prior to or after the sign is installed.

The materials and fabrication for Signing and Delineation work shall conform to the Standard Specifications for State Road and Bridge Construction (1990 Edition) and Special Provisions.

INDEX OF SHEETS

- SIGNING INDEX, SYMBOLS, & GENERAL NOTES
- POST SPACING & SIGN ANGLE DETAILS
- HEIGHT & LATERAL DISTANCE FOR ERECTION
- POSITIONING OF DELINEATORS AND OBJECT MARKERS (TYPE 2 & 3)
- DESIGN & MOUNTING DETAILS FOR DELINEATORS
- DESIGN & MOUNTING DETAILS FOR OBJECT MARKERS (TYPE 2 & 3)
- PLAN SHEETS (INSTALLATIONS)
- PLAN SHEETS (REMOVALS)
- QUANTITIES SHEETS (INSTALLATIONS)
- QUANTITIES SHEET (DELINEATORS & OBJECT MARKERS)
- SUMMARY SHEET (INSTALLATIONS)
- SUMMARY SHEET (REMOVALS)
- RECAPITULATION SHEET
- STANDARD STRUCTURAL SIGN SUPPORTS (WOOD & STEEL POSTS)
- MOUNTING OF SIGNS ON WOOD POSTS
- MOUNTING OF FLAT SHEET SIGNS ON STEEL I-BEAM POSTS
- MOUNTING OF REINFORCED PANEL SIGNS ON I-BEAM POSTS
- DETAILS FOR FLAT SHEET SIGN BLANKS
- DETAILS FOR PROCESSED SIGNS
- DETAILS FOR REINFORCED PANELS
- DETAILS FOR GUIDE SIGN LEGEND
- DETAILS FOR GUIDE SIGNS
- DETAILED SIGN SPECIFICATIONS

Plotted By : @USERNAM@  
 Plot File : @DGN@  
 Plot Date : @SYTIME@

3				
2				
1				
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION  
SIGNING SYMBOL KEY,  
GENERAL NOTES, AND INDEX

#E4026# 07-01-03

FHWA APPROVAL	07-22-2003	APP'D	Steven A. Buckley
DESIGNED	DDG	DETAILED	WSB
DESIGN CK.	SAB	DETAIL CK.	DDG
		QUANTITIES	TRACED
		QUAN. CK.	TRACE CK.