

Plotted By: djb Date: 8/26/2010 2:28:45 PM
 FILE: I:\2005\05789\Geometry\05789-Sidewalk_Coord.tbl.dgn

COORDINATE TABLE					
POINT NO.	NORTH COORDINATE	EAST COORDINATE	STATION	OFFSET	DESCRIPTION
5001	1,682,645.5307	1,607,555.9580	87+49.00	46.60 Lt.	€ Sidewalk P.I. (Match Exist.)
5002	1,682,636.2712	1,607,555.6575	87+58.25	46.17 Lt.	€ Sidewalk P.C. (150' R.)
5003	1,682,611.3141	1,607,552.7419	87+83.17	42.92 Lt.	€ Sidewalk P.R.C. (150' R., 150' R.)
5004	1,682,560.2954	1,607,551.2523	88+34.16	40.73 Lt.	€ Sidewalk P.T. (150' R.)
5005	1,682,545.8728	1,607,553.3110	88+48.61	42.59 Lt.	€ Sidewalk P.C. (50' R.)
5006	1,682,536.1843	1,607,553.7438	88+58.31	42.89 Lt.	€ Sidewalk P.T. (50' R.)
5007	1,682,483.6759	1,607,550.9851	89+10.77	39.41 Lt.	€ Sidewalk P.C. (200' R.)
5008	1,682,469.4429	1,607,550.7446	89+25.00	38.98 Lt.	€ Sidewalk P.T. (200' R.)
5009	1,682,423.4519	1,607,551.6048	89+71.00	39.21 Lt.	€ Sidewalk P.C. (200' R.)
5010	1,682,415.4504	1,607,551.5943	89+79.00	39.09 Lt.	€ Sidewalk P.T. (200' R.)
5011	1,682,344.9133	1,607,550.0910	90+49.51	36.62 Lt.	€ Sidewalk P.C. (200' R.)
5012	1,682,337.9165	1,607,550.0643	90+56.50	36.50 Lt.	€ Sidewalk P.T. (200' R.)
5013	1,682,287.9479	1,607,550.7477	91+06.48	36.50 Lt.	€ Sidewalk P.I. (WCR)
5014	1,682,242.9853	1,607,561.8636	91+51.59	47.00 Lt.	€ Sidewalk P.I. (Begin Sidewalk)
5015	1,682,242.9716	1,607,560.8637	91+51.59	46.00 Lt.	€ Sidewalk P.C. (12.5' R.)
5016	1,682,230.3019	1,607,548.5358	91+64.09	33.50 Lt.	€ Sidewalk P.T. (12.5' R.)
5017	1,681,764.3402	1,607,554.9087	96+30.09	33.50 Lt.	€ Sidewalk P.I.
5018	1,681,604.3004	1,607,553.0971	97+90.09	29.50 Lt.	€ Sidewalk P.I.
5019	1,681,194.4325	1,607,558.7028	102+00.00	29.50 Lt.	€ Sidewalk P.I.
5020	1,681,094.4590	1,607,561.3202	103+00.00	30.75 Lt.	€ Sidewalk P.I.
5021	1,681,043.2138	1,607,562.0211	103+51.25	30.75 Lt.	€ Sidewalk P.I. (End Sidewalk)
5022	1,680,788.2376	1,607,565.5084	106+06.25	30.75 Lt.	€ Sidewalk P.I. (Begin Sidewalk)
5023	1,680,744.4917	1,607,566.1067	106+50.00	30.75 Lt.	€ Sidewalk P.I.
5024	1,680,644.4839	1,607,566.2243	107+50.00	29.50 Lt.	€ Sidewalk P.I.
5025	1,680,107.9684	1,607,573.5621	112+86.57	29.50 Lt.	€ Sidewalk P.I.
5026	1,680,011.1514	1,607,574.9318	113+83.41	29.50 Lt.	€ Sidewalk P.I.
5027	1,679,771.2603	1,607,584.3260	116+23.41	35.50 Lt.	€ Sidewalk P.I.
5028	1,679,401.1967	1,607,589.5612	119+93.51	35.50 Lt.	€ Sidewalk P.C. (200' R.)
5029	1,679,388.2314	1,607,590.1658	120+06.48	35.92 Lt.	€ Sidewalk P.T. (200' R.)
5030	1,679,301.2790	1,607,597.0541	120+93.52	41.58 Lt.	€ Sidewalk P.C. (200' R.)
5031	1,679,288.3137	1,607,597.6588	121+06.49	42.00 Lt.	€ Sidewalk P.T. (200' R.)
5032	1,679,199.8126	1,607,598.9108	121+95.00	42.00 Lt.	€ Sidewalk P.C. (200' R.)
5033	1,679,189.8225	1,607,598.8025	122+04.99	41.75 Lt.	€ Sidewalk P.T. (200' R.)
5034	1,679,099.7491	1,607,595.5754	122+95.01	37.25 Lt.	€ Sidewalk P.C. (200' R.)
5035	1,679,089.7591	1,607,595.4672	123+05.00	37.00 Lt.	€ Sidewalk P.T. (200' R.)
5036	1,678,968.2146	1,607,597.1866	124+26.55	37.00 Lt.	€ Sidewalk P.C. (200' R.)
5037	1,678,951.3635	1,607,598.1372	124+43.42	37.71 Lt.	€ Sidewalk P.T. (200' R.)
5038	1,678,903.2587	1,607,602.8938	124+91.58	41.79 Lt.	€ Sidewalk P.C. (200' R.)
5039	1,678,886.4077	1,607,603.8444	125+08.45	42.50 Lt.	€ Sidewalk P.T. (200' R.)
5040	1,678,825.8548	1,607,604.7011	125+69.01	42.50 Lt.	€ Sidewalk P.C. (200' R.)
5041	1,678,813.8724	1,607,604.5115	125+80.98	42.14 Lt.	€ Sidewalk P.T. (200' R.)
5042	1,678,775.8117	1,607,602.7678	126+19.02	39.86 Lt.	€ Sidewalk P.C. (200' R.)
5043	1,678,763.8293	1,607,602.5782	126+30.99	39.50 Lt.	€ Sidewalk P.T. (200' R.)
5044	1,678,673.8313	1,607,603.8514	127+21.00	39.50 Lt.	€ Sidewalk P.C. (200' R.)
5045	1,678,665.8408	1,607,604.1243	127+29.00	39.66 Lt.	€ Sidewalk P.T. (200' R.)
5046	1,678,630.5078	1,607,606.0385	127+64.35	41.07 Lt.	€ Sidewalk P.C. (200' R.)
5047	1,678,609.2245	1,607,606.0575	127+85.63	40.79 Lt.	€ Sidewalk P.T. (200' R.)
5048	1,678,550.1430	1,607,603.8848	128+44.68	37.78 Lt.	€ Sidewalk P.C. (200' R.)
5049	1,678,539.4885	1,607,603.7517	128+55.33	37.50 Lt.	€ Sidewalk P.T. (200' R.)
5050	1,678,498.5709	1,607,604.3305	128+96.25	37.50 Lt.	€ Sidewalk P.C. (200' R.)
5051	1,678,491.0789	1,607,604.5770	129+03.75	37.64 Lt.	€ Sidewalk P.T. (200' R.)
5052	1,678,398.6293	1,607,609.3543	129+96.25	41.11 Lt.	€ Sidewalk P.C. (200' R.)
5053	1,678,391.1373	1,607,609.6007	130+03.75	41.25 Lt.	€ Sidewalk P.T. (200' R.)
5054	1,678,272.5165	1,607,611.2788	131+22.38	41.25 Lt.	€ Sidewalk P.C. (200' R.)
5055	1,678,267.2797	1,607,611.2843	131+27.62	41.18 Lt.	€ Sidewalk P.T. (200' R.)
5056	1,678,174.5421	1,607,610.1678	132+20.33	38.75 Lt.	€ Sidewalk P.C. (200' R.)
5057	1,678,155.2312	1,607,610.8689	132+39.65	39.18 Lt.	€ Sidewalk P.T. (200' R.)
5058	1,678,096.6644	1,607,615.8365	132+98.28	43.32 Lt.	€ Sidewalk P.C. (200' R.)
5059	1,678,063.2590	1,607,615.8702	133+31.68	42.88 Lt.	€ Sidewalk P.T. (200' R.)
5060	1,678,003.5058	1,607,610.9230	133+91.36	37.09 Lt.	€ Sidewalk P.C. (200' R.)
5061	1,677,986.1745	1,607,610.2428	134+08.68	36.16 Lt.	€ Sidewalk P.T. (200' R.)
5062	1,677,929.8522	1,607,610.4763	134+65.00	35.60 Lt.	€ Sidewalk P.C. (200' R.)
5063	1,677,903.4601	1,607,612.3357	134+91.42	37.09 Lt.	€ Sidewalk P.R.C. (200' R., 200' R.)
5064	1,677,877.0680	1,607,614.1952	135+17.83	38.57 Lt.	€ Sidewalk P.T. (200' R.)
5065	1,677,844.8982	1,607,614.3285	135+50.00	38.25 Lt.	€ Sidewalk P.I. (End Sidewalk)
6001	1,682,478.0747	1,607,450.6382	89+15.00	61.00 Rt.	€ Sidewalk P.C. (50' R.) (Match Exist.)
6002	1,682,468.1539	1,607,451.7711	89+24.94	60.00 Rt.	€ Sidewalk P.T. (50' R.)
6003	1,682,404.1908	1,607,465.6530	89+89.08	47.00 Rt.	€ Sidewalk P.C. (50' R.)
6004	1,682,394.2700	1,607,466.7858	89+99.02	46.00 Rt.	€ Sidewalk P.T. (50' R.)
6005	1,682,288.0568	1,607,468.2385	91+05.24	46.00 Rt.	€ Sidewalk P.C. (200' R.)
6006	1,682,278.5478	1,607,468.5949	91+14.75	45.77 Rt.	€ Sidewalk P.T. (200' R.)
6007	1,682,183.6044	1,607,474.4183	92+09.77	41.25 Rt.	€ Sidewalk P.C. (100' R.)
6008	1,682,173.1432	1,607,474.5117	92+20.23	41.30 Rt.	€ Sidewalk P.T. (100' R.)
6009	1,682,114.0324	1,607,471.9444	92+79.30	44.67 Rt.	€ Sidewalk P.C. (200' R.)
6010	1,682,102.6190	1,607,471.7748	92+90.71	45.00 Rt.	€ Sidewalk P.T. (200' R.)
6011	1,681,965.0008	1,607,473.6569	94+28.34	45.00 Rt.	€ Sidewalk P.C. (200' R.)
6012	1,681,951.7043	1,607,474.2818	94+41.64	44.56 Rt.	€ Sidewalk P.T. (200' R.)
6013	1,681,905.7119	1,607,477.9804	94+87.68	41.49 Rt.	€ Sidewalk P.C. (100' R.)

COORDINATE TABLE					
POINT NO.	NORTH COORDINATE	EAST COORDINATE	STATION	OFFSET	DESCRIPTION
6014	1,681,891.0855	1,607,478.0834	95+02.31	41.58 Rt.	€ Sidewalk P.T. (100' R.)
6015	1,681,833.0539	1,607,474.2388	95+60.28	46.22 Rt.	€ Sidewalk P.C. (150' R.)
6016	1,681,813.5993	1,607,474.2143	95+79.74	46.51 Rt.	€ Sidewalk P.T. (150' R.)
6017	1,681,652.0858	1,607,484.5060	97+41.37	38.43 Rt.	€ Sidewalk P.C. (200' R.)
6018	1,681,634.8336	1,607,484.8594	97+58.63	38.31 Rt.	€ Sidewalk P.T. (200' R.)
6019	1,681,544.3742	1,607,482.8081	98+49.05	41.60 Rt.	€ Sidewalk P.C. (200' R.)
6020	1,681,522.5100	1,607,483.5090	98+70.92	41.20 Rt.	€ Sidewalk P.T. (200' R.)
6021	1,681,400.8603	1,607,494.0899	99+92.71	32.28 Rt.	€ Sidewalk P.C. (200' R.)
6022	1,681,386.2652	1,607,494.8234	100+07.31	31.75 Rt.	€ Sidewalk P.T. (200' R.)
6023	1,681,042.3590	1,607,499.5270	103+51.25	31.75 Rt.	€ Sidewalk P.I. (End Sidewalk)
6024	1,680,787.3829	1,607,503.0142	106+06.25	31.75 Rt.	€ Sidewalk P.I. (Begin Sidewalk)
6025	1,680,743.6370	1,607,503.6125	106+50.00	31.75 Rt.	€ Sidewalk P.I.
6026	1,680,643.6292	1,607,503.7302	107+50.00	33.00 Rt.	€ Sidewalk P.I.
6027	1,680,107.0990	1,607,511.0682	112+86.57	33.00 Rt.	€ Sidewalk P.I.
6028	1,680,010.3111	1,607,512.4374	113+83.36	33.00 Rt.	€ Sidewalk P.I.
6029	1,679,857.0820	1,607,510.7750	115+36.55	36.83 Rt.	€ Sidewalk P.C. (200' R.)
6030	1,679,850.1891	1,607,510.5813	115+43.44	37.12 Rt.	€ Sidewalk P.T. (200' R.)
6031	1,679,824.5510	1,607,509.4184	115+69.06	38.65 Rt.	€ Sidewalk P.C. (200' R.)
6032	1,679,812.6593	1,607,509.2329	115+80.95	39.00 Rt.	€ Sidewalk P.T. (200' R.)
6033	1,679,795.3287	1,607,509.4781	115+98.28	39.00 Rt.	€ Sidewalk P.I. (WCR)
6034	1,679,745.5108	1,607,510.1829	116+48.10	39.00 Rt.	€ Sidewalk P.I. (WCR)
6035	1,679,729.4868	1,607,510.4095	116+64.13	39.00 Rt.	€ Sidewalk P.C. (100' R.)
6036	1,679,702.7106	1,607,514.4554	116+90.96	35.33 Rt.	€ Sidewalk P.R.C. (100' R., 50' R.)
6037	1,679,689.3225	1,607,516.4783	117+04.38	33.50 Rt.	€ Sidewalk P.T. (50' R.)
6038	1,679,663.8983	1,607,516.8379	117+29.80	33.50 Rt.	€ Sidewalk P.C. (50' R.)
6039	1,679,649.0610	1,607,514.8048	117+44.61	35.74 Rt.	€ Sidewalk P.R.C. (50' R., 100' R.)
6040	1,679,617.6297	1,607,510.7789	117+75.98	40.21 Rt.	€ Sidewalk P.T. (100' R.)
6041	1,679,556.0999	1,607,512.7311	118+37.53	39.13 Rt.	€ Sidewalk P.C. (200' R.)
6042	1,679,541.1730	1,607,512.6474	118+52.46	39.43 Rt.	€ Sidewalk P.T. (200' R.)
6043	1,679,484.2897	1,607,510.2036	119+09.30	42.67 Rt.	€ Sidewalk P.C. (200' R.)
6044	1,679,472.8763	1,607,510.0393	119+20.71	43.00 Rt.	€ Sidewalk P.T. (200' R.)
6045	1,679,430.2437	1,607,510.6424	119+63.35	43.00 Rt.	€ Sidewalk P.C. (150' R.)
6046	1,679,416.9724	1,607,511.4193	119+76.63	42.41 Rt.	€ Sidewalk P.T. (150' R.)
6047	1,679,383.0642	1,607,514.9175	120+10.58	39.39 Rt.	€ Sidewalk P.C. (100' R.)
6048	1,679,374.2167	1,607,515.4354	120+19.44	39.00 Rt.	€ Sidewalk P.T. (100' R.)
6049	1,679,366.0787	1,607,515.5505	120+27.57	39.00 Rt.	€ Sidewalk P.I. (WCR)
6050	1,679,315.5538	1,607,516.2653	120+78.10	39.00 Rt.	€ Sidewalk P.I. (WCR)
6051	1,679,284.5386	1,607,516.7041	121+09.12	39.00 Rt.	€ Sidewalk P.C. (200' R.)
6052	1,679,272.7905	1,607,516.5251	121+20.87	39.35 Rt.	€ Sidewalk P.T. (200' R.)
6053	1,679,204.4710	1,607,513.4753	121+89.14	43.36 Rt.	€ Sidewalk P.C. (200' R.)
6054	1,679,182.7399	1,607,513.6872	122+10.87	43.46 Rt.	€ Sidewalk P.T. (200' R.)
6055	1,679,098.6670	1,607,519.0840	122+95.01	39.25 Rt.	€ Sidewalk P.C. (200' R.)
6056	1,679,088.6840	1,607,519.4748	123+05.00	39.00 Rt.	€ Sidewalk P.T. (200' R.)
6057	1,678,966.1188	1,607,521.2086	124+27.57	39.00 Rt.	€ Sidewalk P.I. (WCR)
6058	1,678,915.5939	1,607,521.9234	124+78.10	39.00 Rt.	€ Sidewalk P.I. (WCR)
6059	1,678,901.6869	1,607,522.1201	124+92.01	39.00 Rt.	€ Sidewalk P.C. (200' R.)
6060	1,678,885.7304	1,607,521.7089	125+07.96	39.64 Rt.	€ Sidewalk P.T. (200' R.)
6061	1,678,826.5931	1,607,517.8189	125+67.04	44.36 Rt.	€ Sidewalk P.C. (200' R.)
6062	1,678,810.6366	1,607,517.4076	125+82.99	45.00 Rt.	€ Sidewalk P.T. (200' R.)