


FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
	KANSAS	..		72	..

	Qty	UOM
Lump Sum Bid Items		
Site Clearing and Restoration	1	LS
Mobilization	1	LS
Street Signage	1	LS
Pavement Marking	1	LS
Traffic Control	1	LS
Electrical- Light poles, fixtures, bases, controls and service	1	LS
Paving Items		
Concrete Pavement (4")	148	SY
Roadway Pavement (Reinf.)(8")	531	SY
5" Crushed Rock Base	565	SY
Comb. C & G (6 5/8" & 1 1/2")	255	LF
Mono Edge Curb (6 & 1 1/2")	244	LF
Inlet Hookup	2	EA
Precast Concrete Pavers	250	SF
General Items		
Sawed Joint	1810	LF
Pavement Removed	2927	SY
Conc. &/or Asph. Sdwlk, Drive, &/or Parking Lot Rmd	1934	SY
Comb. C & G Removed	472	LF
Inlet Removed	2	EA
Clean Fill	1450	CY
Decorative Bollards	16	EA
Chainlink Fence (KDOT)	1400	LF
6' Chainlink Fence w/ Barbed Wire	560	LF
Steel Guardrail, 48" Tall	381	LF
Fence Removal	833	LF
Drainage Items		
SWS Pipe RCP 15"	360	LF
SWS Pipe RCP18"	15	LF
SWS 15" RCP Pipe End Section	9	EA
Inlet (2'x2')	2	EA
Inlet (Type 1A)	1	EA
Manhole (Type P w/ Beehive Top)	1	EA
Retrofit Inlet w/ 4'x2' Grate top	2	EA
Ditch Grading (Swales)	640	LF
Landscaping and Amenities		
Clean Fill (Berms)	925	CY
Anti-Graffiti	1	LS
Limestone LedgeStone Wall	11	Tons
Benches	12	EA
Shade Structures	2	EA
Shade Trees (2")	116	EA
Ornamental Trees (1")	121	EA
Evergreen Trees (5-8')	58	EA
Shrubs (3 Gal)	3	EA
Biofiltration Plantings (4" Pots)	2060	EA
Biofiltration Plantings (1- Gal.)	115	EA
Biofiltration Plantings (2- Gal.)	102	EA
Mulch (@ Biofiltration Swales)	27	CY
Biofiltration Planting Mix	166	CY
Gravel (Biofiltration Drain)	9	CY
12" x 48" deep Perforated PVC Pipe (Biofiltration Swale)	9	EA
Filter Fabric	1	LS
12" Wide Reinforced Concrete Edging (Biofiltration Swale)	511	LF
Planting Bed Prep	250	SF
Bermudagrass Sod	17155	SY
Fescue Sod	4625	SY
Tree Relocation	14	EA
Measured Quantity Bid Items		
Concrete Pavement (5")	12,915	SY
Asphalt Pavement (5")	467	SY
Wheelchair Ramp Construction	31	EA
Thickened Edge Concrete	610	LF
6" Wide Curb at Back of Path	160	LF
Standard Driveway Entrance (Reinf.)(8")	4,320	SF
Inlet Sediment Barrier	5	EA
Silt Fence	925	LF

I-135 to K-96 BIKE PATH
RECAPITULATION OF QUANTITIES
WICHITA, KANSAS



Ruggles & Bohm, F.A.
Engineering, Surveying, Land Planning
924 North Main (316) 264-8008
Wichita, Kansas 67203 (316) 264-4621 fax
www.rbkansas.com E-mail: info@rbkansas.com

DRAWING FILE
Title-DTL {RECAP OF QTYS}

PROJECT NUMBER
472-84759

DESIGN	TCR	SHEET 72 OF 72
DRAWN	BDT	
REVIEW		
UTILITY		
DATE	..	