

COLORED STAMPED CONCRETE (6")				
STATION to	STATION	SIDE	SO. YDS.	COLOR & PATTERN
Zetta Road	49+40.67	50+74.20	Lt.	37.0
143rd Street	49+29.21	50+50.64	Rt.	33.6
159th Street	49+49.34	50+50.89	Rt.	28.1
TOTAL			98.7	

CONCRETE PAVEMENT (VALLEY GUTTER)				
STATION	SIDE	SO. YDS.		REMARKS
		8"	10"	
143rd Street				
40+43.06	Lt.	148.3		Cardinal Lane
40+44.91	Rt.	316.0		Cardinal Lane
44+47.45	Lt.	214.6		
45+84.22	Rt.	207.3		Lewis Street
55+38.79	Lt.	83.4		Edgewater Road
58+83.98	Rt.	216.8		Lakeview Drive
59+96.66	Lt.	142.3		Lakeshore Drive
Lakeview Drive				
51+14.61	€	156.1		
159th Street				
41+43.02	Rt.	291.1		Willowbrook Street
58+17.82	Lt.	275.8		Wren Field Drive
TOTAL		156.1	1,895.6	

CONCRETE DRIVEWAY					
STATION	SIDE	WIDTH FT.	RADIUS FT.	SQUARE FEET	
				6"	8"
South Frontage Road					
1627+39.59	Rt.	Var.	30	1,915.6	
1696+44.25	Rt.	35.5	30	1,453.0	
1708+48.10	Rt.	25	30		1,016.0
North Frontage Road					
2698+56.60	Lt.	14.5	25		1,105.0
2744+50.02	Lt.	34.9	25		2,866.3
143rd Street					
59+14.90	Rt.	22.4	25	384.1	
60+21.68	Lt.	12	25	882.2	
Lakeview Drive					
50+80.99	Lt.	10.7	25	287.0	
159th Street					
56+12	Lt.	30	25		964.6
TOTALS				4,921.9	5,951.9

CONCRETE SIDEWALK (4")				
STATION to	STATION	SIDE	WIDTH FT.	AREA SQ. FT.
North Frontage Road				
2680+70.25	2681+89.26	Lt.	6	1,007.8
2681+89.26	2719+96.91	Lt.	6	22,848.6
2721+57.53	2727+30.61	Lt.	6	3,446.2
2729+68.61	2731+04.40	Lt.	6	820.8
2731+04.40	2731+93.58	Lt.	6	858.9
2733+28.39	2734+46.39	Lt.	6	790.6
2734+46.39	2757+93.75	Lt.	6	14,088.0
South Frontage Road				
1616+35.00	1620+43.74	Rt.	6	2,396.0
1622+88.12	1627+12.50	Rt.	6	2,594.2
1627+59.96	1662+99.52	Rt.	6	21,254.8
1664+40.38	1681+48.83	Rt.	6	10,244.8
1681+48.83	1682+67.83	Rt.	6	1,024.3
1683+88.08	1685+00.80	Rt.	6	1,086.4
1685+00.80	1722+15.47	Rt.	6	22,291.0
1723+75.95	1730+42.25	Rt.	6	4,009.4
1732+84.25	1734+16.02	Rt.	6	822.6
1734+16.02	1735+34.04	Rt.	6	766.7
1736+50.72	1737+58.04	Rt.	6	834.3
1737+58.04	1755+56.50	Rt.	6	10,790.3
143rd Street				
39+50.00	40+22.70	Lt.	6	436.9
39+50.01	40+02.72	Rt.	6	316.3
40+67.64	44+20.19	Lt.	6	2,128.5
40+87.11	45+54.99	Rt.	6	2,824.0
44+78.12	47+75.40	Lt.	6	1,783.7
46+13.45	47+62.22	Rt.	6	892.7
47+62.22	48+29.42	Rt.	6	460.2
52+07.64	55+79.06	Rt.	6	2,241.2
52+11.74	55+07.76	Lt.	6	1,774.5
57+22.06	58+49.75	Rt.	6	780.1
57+22.06	59+70.43	Lt.	6	1,488.1
59+14.25	59+27.36	Rt.	6	79.0
60+18.29	61+00.00	Lt.	6	490.3
159th Street				
40+55.23	41+01.81	Rt.	6	279.5
41+90.15	47+93.28	Rt.	6	3,656.0
51+75.99	55+97.00	Lt.	6	2,526.0
56+27.00	57+80.50	Lt.	6	921.1
TOTAL				145,053.8

AC PAVEMENT				
STATION to	STATION	SIDE	AC PAVEMENT 7" (5" BIT BASE)	
			WIDTH FT.	SO. YDS.
Lakeview Dr.				
50+00.00	51+14.61	€	Var.	300.5
TOTAL				300.5

*BRICK PAVERS (CONCRETE)						
STATION to	STATION	SIDE	SIZE	SO. YDS.		PATTERN
				CROSSWALK	MEDIAN	
North Frontage Road						
2679+19.38	2679+47.48	Lt.		44.4		
2680+69.24	2680+77.24	Lt. & Rt.		50.5		
2731+88.75	2732+15.44	Lt.		50.0		
2733+27.39	2733+35.39	Lt. & Rt.		53.9		
South Frontage Road						
1682+60.83	1682+68.83	Lt. & Rt.		50.9		
1683+83.13	1683+94.78	Lt.		33.1		
1735+27.02	1735+35.02	Lt. & Rt.		53.2		
1736+42.30	1736+55.86	Lt.		35.2		
Zetta						
48+23.73	48+31.73	Lt. & Rt.		21.3		
48+46.73	48+65.99	Lt.			28.5	
143rd Street						
48+16.66	48+24.66	Lt. & Rt.		84.0		
48+25.66	48+42.64	Lt. & Rt.			41.6	
48+84.21	50+84.30	Rt.			609.8	
48+96.03	50+95.38	Lt.			611.5	
51+37.40	51+55.48	Rt.			26.6	
51+56.48	51+64.48	Lt. & Rt.		74.1		
159th Street						
48+25.66	48+33.66	Lt. & Rt.		76.3		
48+34.66	48+62.66	Lt. & Rt.			74.1	
49+04.34	50+83.74	Rt.			453.0	
49+15.90	50+95.90	Lt.			453.3	
51+37.33	51+62.48	Rt.			38.0	
51+63.48	51+71.48	Lt. & Rt.		71.9		
TOTAL				698.8	2,336.4	

* Includes Sand Base

WHEELCHAIR RAMP W/ DETECTABLE PANELS					
STATION	SIDE	WIDTH FT.	TYPE I EACH	WIDE MEDIAN EACH	
North Frontage Road					
2679+18.44	Lt.	6	1		
2679+47.74	Rt.	6	1		
2680+73.25	Lt.	6	1		
2680+73.24	Rt.	6	1		
2731+87.97	Lt.	6	1		
2732+14.97	Rt.	6	1		
2733+31.39	Rt.	6	1		
2733+31.39	Lt.	6	1		
2757+93.75	Lt.	6	1		
South Frontage Road					
1627+12.50	Rt.	6	1		
1627+59.96	Rt.	6	1		
1682+64.83	Rt.	6	1		
1682+64.83	Lt.	6	1		
1683+86.07	Lt.	6	1		
1683+92.44	Rt.	6	1		
1735+31.02	Rt.	6	1		
1735+31.02	Lt.	6	1		
1736+44.78	Lt.	6	1		
1736+54.30	Rt.	6	1		
1755+56.44	Rt.	6	1		
143rd Street					
40+02.72	Rt.	6	1		
40+22.70	Lt.	6	1		
40+67.64	Lt.	6	1		
40+87.11	Rt.	6	1		
44+20.19	Lt.	6	1		
44+78.12	Lt.	6	1		
45+54.99	Rt.	6	1		
46+13.45	Rt.	6	1		
48+20.66	Rt.	6	1		
48+20.66	€	6		1	
48+20.66	Lt.	6	1		
51+60.48	Rt.	6	1		
51+60.48	€	6		1	
51+60.48	Lt.	6	1		
55+07.76	Lt.	6	1		
55+79.06	Lt.	6	1		
58+49.75	Rt.	6	1		
59+14.25	Rt.	6	1		
59+70.43	Lt.	6	1		
60+18.29	Lt.	6	1		
159th Street					
41+01.81	Rt.	6	1		
41+90.15	Rt.	6	1		
48+29.66	Rt.	6	1		
48+29.66	€	6		1	
48+29.66	Lt.	6	1		
51+67.48	Rt.	6	1		
51+67.48	€	6		1	
51+67.48	Lt.	6	1		
57+80.50	Lt.	6	1		
58+55.14	Lt.	6	1		
TOTAL			46	4	

COMBINED CURB & GUTTER (AE)									
STATION to	STATION	SIDE	LINEAR FEET				MEDIAN NOSE EACH	REMARKS	
			TYPE I	TYPE II	TYPE III (8")	TYPE III (SPEC.)			
North Frontage Road									
2668+77.47	2678+37.29	Lt.			961.2				
2681+89.26	2719+46.66	Lt.			3,760.9				
2730+02.20	2731+04.40	Lt.			102.2				
2721+91.35	2726+97.03	Lt.			505.7				
2734+46.39	2744+13.38	Lt.			967.5				
2744+86.67	2758+08.04	Lt.			1,333.2				
2668+77.47	2678+37.29	Rt.			959.7				
2681+89.26	2687+42.27	Rt.			553.5				
2690+58.49	2712+29.29	Rt.			2,170.8				
2719+33.55	2719+49.66	Rt.			16.1				
2730+02.20	2731+04.40	Rt.			102.2				
2721+91.35	2726+97.03	Rt.			505.7				
2734+46.39	2740+81.55	Rt.			635.6				
2743+97.81	2758+08.04	Rt.			1,421.9				
South Frontage Road									
1616+85.55	1620+09.28	Lt.			327.0				
1623+46.55	1658+90.93	Lt.			3,556.6				
1661+31.75	1662+51.54	Lt.			120.1				
1664+74.15	1681+48.83	Lt.			1,675.7				
1685+00.80	1689+70.93	Lt.			470.1				
1696+54.57	1718+61.31	Lt.			2,206.7				
1724+27.57	1730+08.67	Lt.			581.5				
1733+13.83	1734+16.02	Lt.			102.2				
1737+58.03	1742+62.31	Lt.			504.3				
1749+26.50	1755+69.43	Lt.			642.0				
1616+35.00	1620+09.28	Rt.			368.3				
1623+46.55	1627+26.71	Rt.			403.6				
1627+52.61	1662+51.54	Rt.							