STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472 84614	:	222	534

CONCRETE PAVEMENT

STATION to STATION		SIDE	CONCRETE PVMT. 12" (AE) (BR. APP.)		CONC. PVMT. 10" UNIFORM (AE)(NRDJ) MAIN LANES		CONC. PVMT. 10" UNIFORM (AE)(NRDJ) INSIDE SHOULDER		CONC. PVMT. 10" VARIABLE (AE)(NRDJ) INSIDE SHOULDER		CONC. PVMT. 10" VARIABLE (AE)(NRDJ) OUTSIDE SHOULDER		4" CEMENT TREATED BASE		10" GEOGRID REINFORCED BASE		6" SUBGRADE							PAVEMENT EDGE WEDGE (ROCK)	REMARKS
																		LIME TREATED			FLY ASH TREATED					
			WIDTH FT.	SQ. YDS.	WIDTH FT.	SQ. YDS.	WIDTH FT.	SQ. YDS.	WIDTH FT.	SQ. YDS.	WIDTH FT.	SQ. YDS.	WIDTH FT.	SQ. YDS.	WIDTH FT.	SQ. YDS.	WIDTH FT.	MANIPULATION SQ. YDS.	† LIME TONS	ø WATER MGAL	MANIPULATION SQ. YDS.	◔ FLY ASH TONS	ø WATER MGAL	TONS	
South Frontage Road																										
1616+35.00	1620+09.57	Lt. & Rt.			Var.	1,424.3									Var.	1,694.4										
1620+09.28	1620+64.74	Lt. & Rt.	40	212.5																						
1622+91.09	1623+46.55	Lt. & Rt.	40	212.5																						
1623+46.55	1662+51.54	Lt. & Rt.			Var.	11,038.3									Var.	13,958.8										
1662+51.54	1662+97.78	Lt. & Rt.	40	188.6																						
1664+27.91	1664+74.15	Lt. & Rt.	40	188.6																						
1664+74.15	1681+48.83	Lt. & Rt.			Var.	7,958.2									Var.	9,262.5										
1685+00.80	1721+81.51	Lt. & Rt.			Var.	9,820.6									Var.	12,293.0										
1721+81.51	1722+30.94	Lt. & Rt.	40	196.6																						
1723+78.14	1724+27.57	Lt. & Rt.	40	196.6																						
1724+27.57	1730+08.67	Lt. & Rt.			Var.	3,027.5									Var.	3,479.8										
1730+08.67	1730+42.25	Lt. & Rt.	60	247.9																						
1732+80.25	1733+13.83	Lt. & Rt.	60	247.9																						
1733+13.83	1734+16.02	Lt. & Rt.			Var.	681.2									Var.	760.7										
1737+58.04	1755+69.43	Lt. & Rt.			Var.	4,842.8									Var.	5,997.4										
Zelta																										
43+97.42	48+68.74	Lt. & Rt.			Var.	1,105.3									Var.	1,281.7										
49+11.79	50+91.47	Lt. & Rt.			Var.	508.5									30	599.0										Intersection
143rd Street																										
39+50.00	47+81.08	Lt. & Rt.			Var.	6,710.3									Var.	8,477.5										
47+81.08	52+11.71	Lt. & Rt.			Var.	8,646.4									Var.	9,559.9										Intersection
51+76.53	61+00.00	Lt. & Rt.	Var.	708.3	Var.	5,783.6									Var.	6,987.0										
Lakeview Drive																										
51+14.61	51+49.90	Lt. & Rt.													Var.	514.0										
159th Street																										
40+55.23	48+01.39	Lt. & Rt.			Var.	5,666.0									Var.	6821.8										
48+01.39	51+75.99	Lt. & Rt.			Var.	8,294.8									Var.	9141.2										Intersection
51+75.99	62+00.00	Lt. & Rt.			Var.	6,656.3									Var.	8055.5										
Ramp P																										
10640+09.95	10640+70.23	Lt. & Rt.			12	80.9					8	53.3	22	147.5			22	147.5	1.8	2.6				16.6	
10640+70.23	10642+00.48	Lt. & Rt.			Var.	181.2					8	115.3	Var.	325.2			Var.	325.2	4.0	5.8				39.0	
10642+00.48	10642+52.03	Lt. & Rt.			16	92.7					8	45.6	26	149.6			26	149.6	1.9	2.7				15.5	
10642+52.03	10645+65.00	Lt. & Rt.			18	643.8					8	274.7	30	1,059.8			30	1,059.8	13.1	18.9				166.2	
Ramp Q																										
20631+46.94	20633+46.94	Lt. & Rt.			12	266.7					10	222.2	24	533.3			24	533.3	6.6	9.5				44.3	
20633+46.94	20633+92.13	Lt. & Rt.			Var.	65.4					Var.	45.9	24	121.2			24	121.2	1.5	2.2				11.0	
20633+92.13	20634+56.59	Lt. & Rt.			Var.	120.9					8	56.6	Var.	191.6			Var.	191.6	2.4	3.4				16.9	
20634+56.59	20635+73.77	Lt. & Rt.			Var.	204.5			Var.	332.8	8	103.2	Var.	709.1			Var.	709.1	8.8	12.6				31.0	
20635+73.77	20638+96.93	Lt. & Rt.			Var.	737.0			6	218.7	8	284.2	Var.	1,383.5			Var.	1383.5	17.1	24.6				198.0	
20638+96.93	20646+32.66	Lt. & Rt.			24	1,961.9			6	497.8	8	643.6	42	3,430.3			42	3430.3	42.4	61.1				367.8	
20646+32.66	20647+62.14	Lt. & Rt.			24	345.3					8	113.3	34	486.7			34	486.7	6.0	8.7				15.9	
20647+62.14	20649+28.67	Lt. & Rt.			Var.	307.2					8	145.7	Var.	489.0			Var.	489.0	6.1	8.7				33.5	
Ramp R																										
10642+54.80	10643+04.80	Lt. & Rt.			18	97.0					8	45.0	30	163.9			30	163.9	2.0	2.9				23.4	
10643+04.80	10646+16.49	Lt. & Rt.			18	623.5					8	277.0	30	1,039.1			30	1039.1	12.9	18.5				140.1	
10646+16.49	10652+91.25	Lt. & Rt.			Var.	2,159.2					8	593.0	Var.	3,074.0			Var.	3074.0	38.0	54.7				292.3	
10652+91.25	10654+41.25	Lt. & Rt.			Var.	335.9					Var.	167.8	Var.	537.9			Var.	537.9	6.7	9.6				19.2	
10654+41.25	10655+10.18	Lt. & Rt.			16	123.2					9.25	70.6	27.25	209.0			27.25	209.0	2.6	3.7					
10655+10.18	10655+89.66	Lt. & Rt.			Var.	121.2					9.25	81.5	Var.	220.2			Var.	220.2	2.7	3.9					
Ramp S																										
10652+85.66	10654+20.66	Lt. & Rt.			Var.	287.1			5.25	35.3	8	119.6	Var.	507.5			Var.	507.5	6.3	9.0					
10654+20.66	10655+79.24	Lt. & Rt.			16	282.0			5.25	92.6	8	140.9	34.75	612.5			34.75	612.5	7.6	10.9					
10655+79.24	10656+72.10	Lt. & Rt.			16	165.1			5.25	54.2	Var.	91.8	Var.	331.6			Var.	331.6	4.1	5.9					
10656+72.10	10658+50.81	Lt. & Rt.			Var.	291.2			5.25	104.2			Var.	435.1			Var.	435.1	5.4	7.7					
Ramp T																										
20661+88.62	20672+77.40	Lt. & Rt.			Var.	3620.0			Var.	568.5	Var.	622.2	Var.	4,965.8			Var.	3,992.0	49.4	71.1	920.5	34.2	16.4		
Ramp U																										
20686+99.95	20698+24.60	Lt. & Rt.			Var.	3312.1			Var.	548.1	Var.	890.4	Var.	5,003.1			Var.	4,132.0	51.1	73.6	871.1	32.3	15.5		
Ramp V																										
10686+14.72	10699+24.35	Lt. & Rt.			Var.	2115.0			Var.	590.2	Var.	790.3	Var.	3,763.5			Var.	3,763.5	46.6	67.0					
Ramp W																										
20704+91.14	20719+31.99	Lt. & Rt.			Var.	2397.5			Var.	711.3	Var.	876.6	Var.	4,273.0			Var.	4,273.0	52.9	76.1					
Ramp X																										
10709+71.70	10718+68.73	Lt. & Rt.			Var.	1988.0			Var.	576.1	Var.	658.4	Var.	3,471.5			Var.	3,471.5	43.0	61.8					
Ramp Y																										
20740+29.75	20748+20.00	Lt. & Rt.			Var.	1763.1			Var.	575.5	Var.	546.6	Var.	3,043.4			Var.	2,556.5	31.6	45.5	486.9	18.1	8.7		
Ramp Z																										
10739+20.19	10748+20.00	Lt. & Rt.			Var.	1371.6			Var.	435.9	Var.	429.0	Var.	2,425.0			Var.	2,425.0	30.0	43.2					
TOTALS THIS SHEET			2,399.5		108,224.3		0.0		5,341.2		8,504.3		43,102.9		98,884.2		40,771.1	504.6	725.9	2,278.5	84.6	40.6	1,430.7	
TOTALS PREVIOUS SHEET			6,120.8		116,942.6		31,468.0		0.0		21,135.1		159,510.1		29,217.8		110,651.8	1,369.1	1,970.5	47,979.5	1,781.3	854.4	530.4	
GRAND TOTALS			8,520.3		225,166.9		31,468.0		5,341.2		29,639.4		202,613.0		128,102.0		151,422.9	1,873.7	2,696.4	50,258.0	1,865.9	895.0	1,961.1	

† Computed at 5% by weight of the top 6" of soil (soil @ 110 lbs./cu. ft.)
◔ Computed at 15% by weight of the top 6" of soil (soil @ 110 lbs./cu. ft.)
ø Computed at 30% by weight of the top 6" of soil (soil @ 110 lbs./cu. ft.)

CITY OF WICHITA

SUMMARY OF QUANTITIES

3:06:57 PM
2/10/2011
T:\35766A\Cadd\Sheets\Summary\EK2GOTY04.dgn
SURV. - PLOT CADD DES. - DR. - TR. CKD. - APP. -