Horizontal Datum: NAD83 State Plane, south zone
Vertical Datum: NAVD88, USGS mean sea level

N

200' 100' 0 200'

GRAPHIC SCALE

W 47TH ST S

S HOOVER RD

BEGIN EXISTING LEVEE SURFACING

3 C-202

RESTORE ACCESS ROAD TO SMOOTH DRIVEABLE CONDITION.
THIS SHALL BE SUBSIDIARY TO THE LEVEE SURFACING BID ITEM.

6 C-202

STABILIZED CONSTRUCTION ENTRANCE 1 C-402

SE

3 C-202

P L

2+00 4+00 6+00 7+49

END LEVEE GRADING
STA. 7+48.57
(ELEV. 1290.00)

1 C-202

PROPOSED RELOCATED LEVEE
(SEE DETAIL 1, SHEET C-202 FOR TYPICAL SECTION)

CENTERLINE OF EXISTING LEVEE TO SERVE AS HAUL ROUTE.
LEVEE TOP TO RECEIVE ASPHALT MILLINGS PER DETAIL 3, SHEET C-202.

3 C-202

REMOVE ALL TREES TO R.O.W. AND ANY TREE THAT WILL CAUSE CONFLICT WITH NEW FENCE TO BE INSTALLED ON R.O.W.
TRIM ALL LIMBS OVERHANGING THE R.O.W.
(DRY SIDE)

BORING LOCATIONS, SEE SHEET C-203 FOR LOGS

S-C-7

B-13

0+00

BEGIN LEVEE GRADING
STA. 0+00
(ELEV. 1289.41)
(END EXISTING LEVEE SURFACING)

APPROX. 100 LF CUT 28' WIDE TO ALLOW DRAINAGE
SEE SHEET C-201 FOR GRADING AND DETAIL 2, SHEET C-202.

SEE SHEET C-201

3 C-202

INSTALL NEW FLOOD CONTROL FENCE

REMOVE ALL TREES WITHIN 50' OF THE LEVEE TOE
(WET SIDE)

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-4630
Fax: (785) 272-4678

CITY OF WICHITA

Levee "C" Freeboard Remediation (Station 410+00 to Railroad) Improvements For the WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE
LICENSED
15855
11/26/2011
KANSAS
PROFESSIONAL ENGINEER

DESIGNED BY: Larry J. Sample, P.E.		DATE: 2011/Jan/26
DWN BY: Staff	CKD BY: LBK	APP BY: LJS
FILE NAME: 05_OVERALL SITE PLAN.dgn		
AMEC PROJ. NO. 5-6150-0001		

OVERALL SITE PLAN

C-200

SHEET 5 OF 15