


STORMWATER DRAIN #378 to serve
RIDGE PORT ADDITION
RIDGE PORT 3RD ADDITION
RIDGE PORT 4TH ADDITION
RIDGE PORT 5TH ADDITION

CITY OF WICHITA, KANSAS

James L. Armour, P.E. City Engineer
 Project Number: 468-84769 O.C.A. Number: 751501



GENERAL NOTES:

- Contractor will be required to provide notice to utility companies a minimum of seventy-two (72) hours prior to any excavation, as follows:

Kansas One-Call	687-2470
-----------------	----------

The Contractor must notify the following in case of an emergency:


Cox Communications	262-4270
Kansas Gas Service	1-888-482-4950
Westar Energy	383-8650
AT&T	268-2245
City of Wichita Water Dept.	268-4563
City of Wichita Sewer Maint.	268-4024
City of Wichita Storm Sewer Maint.	268-4090
City of Wichita Traffic Maint.	268-4034
- Utility service lines, poles, valve boxes, meters, and etcetera are to be adjusted as necessary by others prior to construction unless the plans specifically call for their adjustment by the Contractor or unless the plans specifically identify a utility to be adjusted by its owner during construction. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.
- Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations, in the opinion of the Engineer, that will leave an unsightly appearance will not be approved. All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps. of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.
- Trees and shrubs in public right-of-way which are in direct conflict with proposed new construction shall be removed by the Contractor with the Engineer's approval. Trees and shrubs which are not in direct conflict with proposed new construction shall be saved and protected from damage.
- Existing Wetlands area to remain undisturbed and shall be protected with Yellow Caution Tape. Protection shall be approved by the Engineer prior to beginning construction. Cost Incidental to "Site Restoration"
- U/G Irrigation System In Area (not field verified). The Contractor shall be required to repair any damage which may occur during construction. Coordinate repair work with Brandon Hay with Ridge Port H.O.A. at (316)640-8533. Cost Incidental to "Site Restoration"
- Bore log information is available upon request from Baughman Co., P.A. 262-7271
- The Contractor shall give all property owners and/or tenants of developed property abutting the construction of this project a minimum of ten (10) days notice prior to start of construction.
- The Contractor shall be responsible for preserving property irons. The Contractor will be required to re-establish any property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed land surveyor in accordance with state laws.
- All existing and proposed erosion control measures including silt fencing, erosion control mat, straw bales, inlet barriers, and const. entrance shall be maintained throughout construction by the contractor and until project is accepted by the City of Wichita. The on-site engineer shall complete weekly reports on the status of erosion control measures. The contractor shall be required to comply with maintenance and/or replacement of erosion control measures as determined by the on-site engineer until project is accepted by City of Wichita.
- All areas disturbed by construction shall be seeded and mulched as follows: (Permanent Seeding)
 SEED -- Kansas Premium Fescue Blend; 8#/1000 Sq. Ft.
 FERTILIZER -- 12-24-12 Ratio at 350 Lbs./Ac.
 MULCH -- 2 Tons Prairie Hay / Acre
 All costs associated with seeding shall be included in bid item "Project Seeding"

Benchmarks

- BM #1 - City Disk at northeast corner of bridge for Big Slough at 29th St North.
 Elev. = 1330.34 (NAVD 88)
- BM #2 - Top of T-Post. 47' W. & 34' N. of the SW corner of Lot 4, Block 4, Ridge Port Addition.
 Elev. = 1322.44 (NAVD 88)
- BM #3 - Top of T-Post. 95' N & W of the northwest corner of bridge for Big Slough at 29th St North.
 Elev. = 1322.44 (NAVD 88)

Sheet Index

Title Sheet	1
Weir Plan/Profile	2-3
Erosion Control Plan	4
Erosion Control BMP Details	5-8
Coordinate Sheet	9



Vicinity Map



Baughman
 Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0148
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

Benefit District: