


PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
472-84817 PHASE I	2011	24	113

SIDEWALK COORDINATE TABLE					
POINT NO.	NORTH COORDINATE	EAST COORDINATE	STATION	OFFSET	DESCRIPTION
5000	1,693,604.8085	1,623,145.7271	47+94.59	55.56' Lt.	€ Sidewalk P.I. (Begin Sidewalk Match Exist.)
5001	1,693,605.2267	1,623,129.2930	47+99.81	72.00' Lt.	€ Sidewalk P.I.
5002	1,693,723.7376	1,623,132.4906	49+13.12	72.00' Lt.	€ Sidewalk P.C. (30' R.)
5003	1,693,737.9842	1,623,136.5312	49+27.47	68.35' Lt.	€ Sidewalk P.T. (30' R.)
5004	1,693,752.0006	1,623,144.6638	199+37.00	55.69' Rt.	€ Sidewalk P.I.
5005	1,693,756.3280	1,623,144.5978	199+37.00	51.36' Rt.	€ Sidewalk P.I. (WCR)
5006	1,693,752.0017	1,623,059.8539	198+52.20	54.39' Rt.	€ Sidewalk P.I. (Begin Sidewalk)
5007	1,693,753.0080	1,623,067.3395	198+59.70	53.50' Rt.	€ Sidewalk P.I. (End Trans. From Exist.)
5008	1,693,753.5830	1,623,105.0495	198+97.41	53.50' Rt.	€ Sidewalk P.C. (30' R.)
5009	1,693,752.0123	1,623,115.0969	199+07.44	55.22' Rt.	€ Sidewalk P.T. (30' R.)
5010	1,693,749.1930	1,623,123.4536	199+15.75	58.17' Rt.	€ Sidewalk P.C. (30' R.)
5011	1,693,747.6298	1,623,132.2346	49+37.00	72.90' Lt.	€ Sidewalk P.T. (30' R.)
5012	1,693,747.3670	1,623,141.9753	49+37.00	63.16' Lt.	€ Sidewalk P.I.
5013	1,693,748.3519	1,623,142.5467	49+38.00	62.61' Lt.	€ Sidewalk P.I.
5014	1,693,748.0682	1,623,153.0614	49+38.00	52.09' Lt.	€ Sidewalk P.I. (WCR)
5015	1,693,856.9605	1,623,143.0636	199+37.00	49.29' Lt.	€ Sidewalk P.I. (WCR)
5016	1,693,861.5090	1,623,142.9942	199+37.00	53.84' Lt.	€ Sidewalk P.I.
5017	1,693,878.5909	1,623,155.5784	50+71.00	49.76' Lt.	€ Sidewalk P.I.
5018	1,693,878.6807	1,623,159.8961	50+71.00	45.45' Lt.	€ Sidewalk P.I. (WCR)
5019	1,693,871.6613	1,623,150.4734	50+64.18	55.01' Lt.	€ Sidewalk P.I.
5020	1,693,881.1714	1,623,131.6945	50+74.08	73.59' Lt.	€ Sidewalk P.I. (End Sidewalk Match Exist.)
5021	1,694,056.0772	1,623,129.0185	52+49.00	72.63' Lt.	€ Sidewalk P.I. (Begin Sidewalk Match Exist.)
5022	1,694,060.0834	1,623,129.2730	52+53.00	72.29' Lt.	€ Sidewalk P.I. (End Trans. To 4' From Exist.)
5023	1,694,085.2080	1,623,135.0108	52+78.00	66.03' Lt.	€ Sidewalk P.I. (Begin Trans. From 4' to Exist.)
5024	1,694,089.2256	1,623,135.7898	53+82.00	65.17' Lt.	€ Sidewalk P.I. (End Sidewalk Match Exist.)
5025	1,694,164.6090	1,623,153.4780	53+57.00	45.92' Lt.	€ Sidewalk P.I. (Begin Sidewalk Match Exist.)
5026	1,694,177.2630	1,623,151.1337	53+69.70	48.00' Lt.	€ Sidewalk P.I. (End Trans. To 4' From Exist.)
5027	1,694,201.2579	1,623,150.6349	53+93.70	48.00' Lt.	€ Sidewalk P.I. (Begin Trans. From 4' to Exist)
5028	1,694,213.5982	1,623,152.1747	54+06.01	46.20' Lt.	€ Sidewalk P.I. (End Sidewalk Match Exist.)
5029	1,694,363.5880	1,623,150.0927	55+56.01	45.17' Lt.	€ Sidewalk P.I. (Begin Sidewalk Match Exist.)
5030	1,694,375.4429	1,623,147.0136	55+67.92	48.00' Lt.	€ Sidewalk P.I. (End Trans. To 4' From Exist.)
5031	1,694,399.4524	1,623,146.5145	55+91.94	48.00' Lt.	€ Sidewalk P.I. - 4'
5032	1,694,412.6423	1,623,152.4980	56+05.00	41.74' Lt.	€ Sidewalk P.I. - 4'
5033	1,694,492.6832	1,623,153.6346	56+85.00	38.94' Lt.	€ Sidewalk P.I. - 4'
5034	1,694,507.7931	1,623,158.7652	57+00.00	33.50' Lt.	€ Sidewalk P.I. - 4'
5035	1,694,528.7885	1,623,158.3287	57+21.00	33.50' Lt.	€ Sidewalk P.I. (Begin S/W 5' Trans.)
5036	1,694,533.7875	1,623,158.2248	57+26.00	33.50' Lt.	€ Sidewalk P.I. (End S/W 5' Trans. Match Exist.)
5037	1,693,586.3645	1,623,248.9351	47+78.94	48.11' Rt.	€ Sidewalk P.I. (Begin Sidewalk)
5038	1,693,596.1641	1,623,246.9430	47+88.68	45.85' Rt.	€ Sidewalk P.I. (End Trans. From Exist.)
5039	1,693,605.1882	1,623,245.1086	47+97.65	43.77' Rt.	€ Sidewalk P.C. (13' R.)
5040	1,693,620.3302	1,623,254.4656	48+13.04	52.72' Rt.	€ Sidewalk P.R.C.
5041	1,693,632.5318	1,623,264.0785	48+25.50	62.00' Rt.	€ Sidewalk P.T. (13' R.)
5042	1,693,677.0156	1,623,265.2787	48+70.00	62.00' Rt.	€ Sidewalk P.C. (30' R.)
5043	1,693,692.0847	1,623,261.6838	48+84.97	58.00' Rt.	€ Sidewalk P.R.C.
5044	1,693,707.1538	1,623,258.0890	48+99.93	54.00' Rt.	€ Sidewalk P.T. (30' R.)
5045	1,693,745.3900	1,623,252.3205	49+38.00	47.20' Rt.	€ Sidewalk P.I. (WCR)
5046	1,693,745.2067	1,623,259.1157	49+38.00	54.00' Rt.	€ Sidewalk P.I.
5047	1,693,756.8930	1,623,276.2152	200+68.00	53.58' Rt.	€ Sidewalk P.I.
5048	1,693,765.6723	1,623,275.9805	200+68.00	44.80' Rt.	€ Sidewalk P.I. (WCR)
5049	1,693,885.5744	1,623,303.1826	50+74.91	97.95' Rt.	€ Trail P.C. (Begin Trail, 30' R.)
5050	1,693,881.3533	1,623,288.4510	50+71.00	83.14' Rt.	€ Trail P.T. (30' R.)
5051	1,693,880.8226	1,623,262.9255	50+71.00	57.61' Rt.	€ Trail P.I. (WCR)
5052	1,693,872.4064	1,623,273.1273	200+68.00	61.97' Lt.	€ Trail P.I. (WCR)
5053	1,693,886.0272	1,623,272.7133	50+76.00	67.50' Rt.	€ Trail P.I.
5054	1,693,942.0151	1,623,271.5494	51+32.00	67.50' Rt.	€ Trail P.C. (30' R.)
5055	1,693,965.0571	1,623,265.0571	51+55.75	61.50' Rt.	€ Trail P.R.C.
5056	1,693,989.2528	1,623,258.5647	51+79.50	55.50' Rt.	€ Trail P.T. (30' R.)
5057	1,694,310.0110	1,623,251.8963	55+00.32	55.50' Rt.	€ Trail P.I.
5058	1,694,380.1833	1,623,247.8279	55+70.57	52.89' Rt.	€ Trail P.I. (End Trail)

Note:
All Sidewalk 6' Unless Otherwise Noted
All Trail 10'

 <p>CITY OF WICHITA PUBLIC WORKS & UTILITIES ENGINEERING DIVISION</p>	SIDEWALK COORDINATE TABLE		
	CITY ENGINEER JAMES L. ARMOUR, P.E., L.S.		
	PROJECT NUMBER 472-84817 PHASE I	OCA NUMBER 770005	DATE 11/2011
	CITY ENGINEER'S OFFICE CITY HALL - SEVENTH FLOOR 455 NORTH MAIN STREET WICHITA, KANSAS 67202-1620 (316) 268-4501		DESIGN DRAWN SHEET 24 of 113

Plotted on: Tuesday, September 27, 2011 09:38 AM
 Plot Queue: \\ovp\00\VP\TBWLP
 Pen Table: \\ovp\00\Jobs\4809\Highway\Library\lib\pen\CC-22x36.pen
 Design Filename: \\ovp\00\Jobs\4809\Highway\CD\Detail\fig_coord\coordinate-geometry.dgn



\\ovp\00\Jobs\4809\Highway\CD\Detail\fig_coord\coordinate-geometry.dgn