

UNIVERSITY AVENUE				
STA	CUT(S.F.)	FILL(S.F.)	CUT(C.Y.)	FILL(C.Y.)
0+00	0.00	0.00		
0+66.37	33.98	13.22	83.53	32.50
1+00	24.26	28.21	30.22	35.14
2+00	30.78	21.87	114.00	81.00
2+34.67	35.68	21.26	45.82	27.30
2+34.68	0.00	0.00	0.00	0.00
TOTAL			273.56	175.93

SUMMARY OF EARTHWORK

