

DRIVEWAY PAVEMENT						DRIVEWAY ITEMS ON PRIVATE PROPERTY			
STATION	SIDE	CONCRETE DRIVEWAY 8" (SQ.YD.)	AC PAVMT. 6" ☆ (SQ.YD.)	P (FT.)	L (FT.)	WIDTH (FT.)	CONCRETE DRIVEWAYS 8" (SQ.YD.)	AC PAVEMENT 6" DRIVEWAYS (SQ.YD.)	CONCRETE C&G TYPE 1 (L.F.)
<b>135TH ST. WEST</b>									
49+86.84	Lt.	46.02		16.31	16.31	22.00			
51+43.85	Rt.	100.24		21.99	21.99	30.00			
56+74.40	Rt.	71.74		39.50	39.50	12.00			
68+68.81	Rt.	97.74		29.50	29.50	24.00			
74+73.71	Rt.	61.69		29.50	29.50	13.00			
79+69.04	Rt.	75.62		29.50	29.50	17.25			
80+98.32	Rt.	84.86		29.50	29.50	20.08			
81+47.52	Rt.	61.86		29.50	29.50	13.06			
85+06.06	Rt.	76.05		29.50	29.50	17.38			
86+52.77	Rt.	60.50		29.50	29.50	12.63			
87+91.20	Rt.	82.70		29.50	29.50	19.41			
89+67.08	Rt.	96.28		29.50	29.50	23.55			
90+36.48	Lt.	57.92		29.50	29.50	12.00			
91+03.42	Rt.	101.02		29.50	29.50	22.25			
92+70.35	Rt.	90.21		29.50	35.50	22.00		26.13	
93+06.65	Rt.	54.15		29.50	35.50	11.00		7.33	
93+84.05	Rt.	96.96		27.89	27.89	25.11			
94+79.88	Lt.	97.28		23.37	23.37	30.00			
96+01.03	Rt.	171.46		29.90	31.75	56.08		11.48	1.81
96+71.90	Lt.	57.57		24.29	24.29	26.00	3.44		
97+45.41	Lt.	58.54		16.25	16.25	24.78			
99+00.12	Lt.	50.57		16.25	16.25	24.00			
101+22.22	Rt.	69.23		16.25	27.69	27.69	40.62		
102+84.44	Rt.		87.56	20.94	27.61	29.42		21.79	
103+85.16	Rt.		90.26	24.67	24.67	25.95			
105+05.29	Rt.		71.81	29.12	29.12	16.28			
106+86.99	Rt.		120.66	35.85	35.85	25.93			
<b>21ST ST. NORTH</b>									
41+63.40	Rt.		46.43	16.89	16.89	15.09			
42+61.03	Rt.		44.25	14.45	14.45	17.47			
45+03.74	Lt.		129.78	41.63	41.63	24.00			
52+94.09	Rt.	126.56		29.24	29.24	27.09			
55+15.60	Rt.		121.01	30.12	30.12	23.33			
TOTAL		1,946.77	711.76				44.06	66.73	1.81

P = Distance from Back-of-curb to Right-of-way Line  
L = Distance from Back-of-curb to Limit of Driveway Paving  
☆ = See Sht. 63 for Asphalt Drive Details

### REINFORCED CONCRETE VALLEY GUTTER

STATION	SIDE	CONC. PAVMT. (VG) 8" (REINF.) (SQ.YD.)	CRUSHED ROCK HOOKUP 6" (SQ.YD.)	REMARKS
<b>135TH SIDEROADS:</b>				
64+31.59	Lt.	185.84		KIWI ST.
73+67.59	Lt.	258.51		RIDGEPOINT
84+41.35	Lt.	258.91		JAMESBURG
85+11.30	Rt.	153.28	52.35	WILLOUGHBY
TOTAL		856.74	52.35	

### MEDIAN PAVERS

LOCATION	QUANTITY (SQ.YD.)	REMARKS
<b>21ST ST. NORTH</b>		
46+66.58 to 49+18.46	83.96	
50+85.48 to 52+88.09	67.54	
TOTAL	151.50	

### EARTHWORK

STATION TO STATION	PAVEMENT REMOVAL (SQ.YD.)	EXCAVATION SIDEWALK REMOVAL (SQ.YD.)	COMMON		COMPACTION			REMARKS
			(CU. YD.)	VMF	95% COMPACTION (CU. YD.)	90% COMPACTION (CU. YD.)	SELECT SOIL (CU. YD.)	
<b>135TH ST. WEST</b>								
47+83.56 to 99+15.969	15,906.31	1,119.09	24,081		2,041			
99+15.96 to 100+85.48	1,344.69		1,826		496			
100+85.48 to 107+25.48	1,871.65		463		855			
<b>21ST ST. NORTH</b>								
41+34.50 to 49+15.96	4,129.62	94.01	1,827		437			
50+85.48 to 58+36.87	3,806.01	143.80	1,386		760			
<b>13TH ST.</b>								
110+35.00 to 111+45.00	316.20		0		0			
<b>SIDE ROADS</b>								
KIWI, RIDGEPOINT, JAMESBURG			1,596		2			
<b>BLATTNER DITCH</b>								
11+40 to 20+14	316.20		6,393		0			
<b>SILVERTON SWALE</b>								
58+50 to 65+31	316.20		6,237		578			
<b>HERITAGE GRADING</b>								
GARCIA GRADING			0		2,330			
TOTAL	27,374.48	1,356.90	45,079		7,500			

≠ Items included in this column include Sidewalk Removal, Paved Driveway Removal, Bus Pad Removal and Parking Lot Removal

### MAILBOX REM/REPL

STATION	SIDE
<b>135TH ST. WEST</b>	
56+88.95	Rt.
75+00.03	Rt.
79+54.77	Rt.
81+09.86	Rt.
85+25.01	Rt.
86+73.99	Rt.
88+10.86	Rt.
89+42.86	Rt.
90+09.07	Lt.
91+25.30	Rt.
92+52.23	Rt.
94+01.64	Rt.
96+56.38	Lt.
98+82.55	Lt.
101+50.20	Rt.
103+06.57	Rt.
103+70.57	Rt.
104+85.17	Rt.
106+62.54	Rt.
<b>21ST ST. NORTH</b>	
42+84.27	Rt.
TOTAL	20

### STORM SEWER REMOVAL

STATION	OFFSET	SIZE/TYPE	LENGTH
<b>135TH ST. WEST</b>			
49+63.32	14.43' Lt.	15" CMP	40.0'
51+44.75	26.90' Rt.	24" CMP	58.6'
55+64.16	C.L.	36" CMP	37.2'
55+73.31	51.61' Rt.	15" CMP	13.1'
55+73.63	C.L.	36" CMP	37.5'
56+73.66	20.45' Rt.	24" CMP	20.3'
58+86.98	21.52' Lt.	24"x15" RCPHE	77.7'
68+70.65	20.07' Rt.	18" CMP	40.6'
71+34.72	33.15' Lt.	42" RCP	86.7'
74+78.16	17.15' Rt.	24" CMP	26.4'
79+58.67	33.06' Lt.	42" RCP	88.1'
79+68.66	19.02' Rt.	15" CMP	30.4'
80+97.49	19.17' Rt.	18" CMP	22.6'
81+47.34	18.83' Rt.	18" CMP	14.5'
83+55.91	18.67' Rt.	15" RCP/CMP	34.0'
85+06.08	16.09' Rt.	15" CMP	24.7'
86+53.99	16.88' Rt.	15" CMP	26.3'
87+92.64	17.88' Rt.	15" CMP	24.2'
89+66.64	18.12' Rt.	18" CMP	29.6'
90+40.70	14.48' Lt.	12" CMP	28.5'
91+03.57	20.09' Rt.	18" RCP	25.7'
97+46.39	26.67' Rt.	36" RCP	32.1'
99+42.59	5.28' Rt.	10" PVC	38.2'
99+43.18	14.48' Lt.	CURB INLET	
101+28.66	37.13' Rt.	24" CMP	31.6'
101+28.85	30.97' Rt.	24" CMP	30.6'
102+84.07	34.23' Rt.	18" CMP	31.4'
102+84.40	29.46' Rt.	18" CMP	31.4'
103+88.75	29.98' Rt.	18" CMP	30.4'
103+88.99	35.63' Rt.	18" CMP	30.4'
104+39.83	C.L.	24"x36" RCPHE	40.6'
104+44.12	C.L.	24"x36" RCPHE	40.8'
105+04.74	29.76' Rt.	24" CMP	30.6'
<b>21ST ST. NORTH</b>			
45+03.74	39.62' Lt.	36" CMP	34.6'
48+15.84	4.01' Rt.	18" CMP	75.0'
50+49.74	C.L.	42" CMP	64.8'
50+61.21	C.L.	42" CMP	64.8'
52+92.82	44.50' Rt.	24" RCP	42.3'
52+93.22	38.12' Rt.	24" RCP	41.7'
55+16.05	38.72' Lt.	24" CMP	36.0'
<b>13TH ST. NORTH</b>			
110+82.9	C.L.	5'x3' CMPHE	32.2'
110+90.5	C.L.	8'x3' CMPHE	36.3'
110+97.7	C.L.	5'x3' CMPHE	35.4'
110+76.06	85.36' Rt.	36" RCP	27.2'
TOTAL			1645.1'

### A.C. PAVEMENT

LOCATION	A.C. Pvmnt. 7" (5" bit base) (SQ.YD.)	A.C. Pvmnt. 5" (3" bit base) (SQ.YD.)	REMARKS
<b>135TH ST. WEST</b>			
47+83.56 to 99+15.96	22,436.37		
100+85.48 to 107+25.48	3,428.87		
<b>21ST ST. NORTH</b>			
41+34.50 to 49+15.96	4,556.28		
50+85.48 to 58+36.87	4,514.63		
<b>13TH ST.</b>			
110+35.00 to 111+45.00	316.29		
<b>SIDE ROADS - KIWI</b>			
58+88.03		84.53	
<b>SIDE ROADS - RIDGEPOINT</b>			
71+35.23		571.83	
<b>SIDE ROADS - JAMESBURG</b>			
79+60.47		449.99	
TOTAL	35,410.82	1,106.35	

### SIDEWALK CONSTRUCTION

STATION TO STATION	SIDE	4" (SQ. FT.)	8" (SQ. FT.)	WHEELCHAIR RAMP (EACH)
<b>135TH ST. WEST</b>				
49+71.40 to 49+75.84	Lt.	44.44		
49+97.84 to 58+63.20	Lt.	8,653.72		1
49+71.40 to 51+28.85	Rt.	944.68		
51+58.85 to 56+68.40	Rt.	3,057.32		
56+80.40 to 68+56.81	Rt.	7,058.47		
59+12.90 to 71+00.47	Lt.	11,875.64		2
68+80.81 to 74+67.21	Rt.	3,518.50		
71+70.32 to 79+25.51	Lt.	7,551.77		2
74+80.21 to 79+60.42	Rt.	2,881.24		
79+77.67 to 80+88.28	Rt.	663.68		
79+87.85 to 90+30.48	Lt.	10,352.63		1
81+08.37 to 81+40.99	Rt.	195.75		
81+54.05 to 83+39.82	Rt.	1,114.60		1
83+78.73 to 84+97.37	Rt.	711.85		1
85+14.75 to 86+46.46	Rt.	790.22		
86+59.09 to 87+81.49	Rt.	734.45		
88+00.90 to 89+55.30	Rt.	926.38		
89+78.85 to 89+83.85	Rt.		30.32	
89+83.85 to 90+92.42	Rt.	651.10		
90+42.48 to 94+64.88	Lt.	4,223.98		
91+14.42 to 91+24.42	Rt.		60.00	
91+24.42 to 92+59.35	Rt.	791.54		
92+81.35 to 93+01.15	Rt.		118.81	
93+12.15 to 93+71.49	Rt.	356.08		
93+96.60 to 95+79.17	Rt.	1,095.18		
94+94.88 to 96+58.90	Lt.	1,640.23		
96+22.89 to 97+33.02	Rt.	660.91		
96+84.90 to 98+88.12	Lt.	2,031.74		
97+57.80 to 99+58.10	Rt.	1,304.30		2
99+12.12 to 99+53.92	Lt.	459.54		2
100+45.25 to 100+56.98	Rt.	134.99		2
100+46.14 to 100+56.98	Lt.	146.63		2
<b>KIWI ST.</b>				
RIDGEPOINT	Lt.	103.70		
JAMESBURG	Lt.	507.29		
	Lt.	240.01		
TOTAL		75,422.56	209.13	16

### CURB AND GUTTER, COMBINED

STATION TO STATION	SIDE	TYPE 1	TYPE 2	TYPE 3
<b>135TH ST. WEST</b>				
49+71.40 to 83+16.02	Rt.	3,344.87		
49+71.40 to 58+40.57	Lt.	869.41		
59+35.53 to 70+77.87	Lt.	1,142.34		
71+92.96 to 79+02.88	Lt.	709.91		
80+17.86 to 99+65.96	Lt.	1,977.06		
84+02.02 to 99+67.34	Rt.	1,596.22		
100+32.80 to 102+25.48	Lt.	221.88		
100+35.49 to 102+25.48	Rt.	219.56		
<b>21ST ST. NORTH</b>				
41+34.50 to 43+05.76	Rt.		171.28	
46+60.58 to 49+15.96	Rt.	255.37		
46+60.58 to 49+15.96	Lt.	255.37		
46+66.58 to 49+18.46	Rt.		251.86	
46+66.58 to 49+18.46	Lt.		251.86	
50+85.48 to 52+88.09	Rt.		202.61	
50+85.48 to 52+88.09	Lt.		202.61	
50+85.48 to 53+36.87	Rt.	251.39		
50+85.48 to 53+36.87	Lt.	251.39		
<b>SIDE ROADS - KIWI</b>				
58+70.57	Lt.	13.41		
59+05.03	Lt.	13.60		
<b>SIDE ROADS - RIDGEPOINT</b>				
71+07.87	Lt.	126.50		
71+32.98 to 71+39.68	Lt.			