

GENERAL NOTES

1. Contractor will be required to provide notice to utility companies a minimum of twenty-four (24) hours prior to any excavation, as follows:

Kansas One-Call 687-2470

The Contractor must notify the following in case of an emergency:

Cox Communications 262-4270
or 263-2061

Westar Energy/

Kansas Gas & Electric Company 1-888-482-4950

Southwestern Bell Telephone Company 1-571-2611

City of Wichita Water Department 268-4908

City of Wichita Sewer Department 268-4071

Aquila Natural Gas 941-1608

or 1-800-303-0357

2. Ex. utilities and their locations, as shown on the plans, represent the best information obtainable for design. Location information has been obtained from the various utility companies and is either from company record drawings or company-provided field locations. The Contractor will be required to work around existing utilities which do not conflict with proposed construction.
3. The Contractor to verify utility locations prior to construction of this project.
4. Utility service and installation shall be coordinated with the respective utility owners. Contacts are:
- | | | |
|-----------------------|---------------|----------|
| Kansas Gas Service | Jim Coe | 832-3126 |
| Westar Energy | Miles Capps | 261-6251 |
| Aquila Networks | Calvin Briggs | 942-8811 |
| Wichita Water & Sewer | Bill Perkins | 268-4555 |
| Southwestern Bell | Jim Toben | 268-2759 |
| Cox Communications | Brian Ring | 262-4270 |
5. All lawn/turf areas disturbed by construction of proposed improvements shall be restored with sod. All sod work shall be in accordance with the City of Wichita standard specifications and the City of Wichita administrative regulation No. AR78 which governs cleanup and replacement following construction. All costs for this work shall be subsidiary to the lump sum price bid for "Site Restoration."
6. Traffic affected by the construction of this project shall be handled in accordance with the latest edition of the Manual on Uniform Traffic Control Devices.
7. Areas over excavated in pavement removal shall be filled to subgrade elevation and compacted to 95% Standard Density.
8. Properties within the project may have underground irrigation systems (lawn sprinklers) which conflict with new construction. Contractor shall remove such components as needed during construction of the project. The irrigation system shall be reinstalled in like kind before project completion. Any irrigation system modifications required because of project improvements shall be coordinated with the property owner. Portions of underground irrigation systems not in conflict with new construction shall be protected from damage and shall remain in place. All work related to underground irrigations/sprinklers shall be subsidiary to Site Restoration.
9. The contractor shall be responsible for preserving property irons. The contractor will be required to re-establish any property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed land surveyor in accordance with state laws.
10. Construction shall be in accordance with the City of Wichita standard construction practices.
11. It is the contractor's responsibility to visit this site to better understand the extent of site clearing and restoration to be performed. Site Clearing and Restoration shall include all costs for removal of items which a pay item is not provided.
12. Temporary Pavement required for adjacent street and business access shall be subsidiary to the "Traffic Control" bid item.
13. Section line, base line is equivalent to center line of pavement improvements.
14. Pedestrian Crossing Signals and a Paved Surface are to be maintained at all times. Maintain one entrance to school at all times.

City of Wichita Bike Path Expansion
General Notes
Wichita, KS



PROJECT NUMBER
472-84932

KEM NO. 05168	FILE quantity	DATE 08/2011	SHEET 2
DESIGN KM	DRAWN GP	REVISED	OF 112

516 S. Market,
Wichita, KS 67202

316/264-0242